

**DS-7200-SH/SV&DS-7300-SH Series DVR**  
**USER MANUAL**

## Regulatory Information

### FCC Information

**FCC compliance:** This equipment has been tested and found to comply with the limits for a digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference in which case the user will be required to correct the interference at his own expense.

### FCC Conditions

This device complies with part 15 of the FCC Rules. Operation is subject to the following two conditions:

1. This device may not cause harmful interference.
2. This device must accept any interference received, including interference that may cause undesired operation.

### EU Conformity Statement



This product and - if applicable - the supplied accessories too are marked with "CE" and comply therefore with the applicable harmonized European standards listed under the Low Voltage Directive 2006/95/EC, the EMC Directive 2004/108/EC.



2002/96/EC (WEEE directive): Products marked with this symbol cannot be disposed of as unsorted municipal waste in the European Union. For proper recycling, return this product to your local supplier upon the purchase of equivalent new equipment, or dispose of it at designated collection points. For more information see: [www.recyclethis.info](http://www.recyclethis.info).



2006/66/EC (battery directive): This product contains a battery that cannot be disposed of as unsorted municipal waste in the European Union. See the product documentation for specific battery information. The battery is marked with this symbol, which may include lettering to indicate cadmium (Cd), lead (Pb), or mercury (Hg). For proper recycling, return the battery to your supplier or to a designated collection point. For more information see: [www.recyclethis.info](http://www.recyclethis.info).

Thank you for purchasing our product. If there is any question or request, please do not hesitate to contact dealer.

This manual is applicable to **DS-7204HVI-SH, DS-7208HVI-SH, DS-7216HVI-SH; DS-7204HFI-SH, DS-7208HFI-SH, DS-7216HFI-SH; DS-7204HWI-SV; DS-7204HWI-SH, DS-7208HWI-SH, DS-7216HWI-SH; DS-7204HVI-SV, DS-7208HVI-SV, DS-7216HVI-SV; DS-7304HFI-SH, DS-7308HFI-SH, DS-7316HFI-SH; DS-7304HWI-SH, DS-7308HWI-SH, DS-7316HWI-SH series DVR.**

This manual may contain several technically incorrect places or printing errors, and the content is subject to change without notice. The updates will be added into the new version of this manual. We will readily improve or update the products or procedures described in the manual.

## Preventive and Cautionary Tips

Before connecting and operating your device, please be advised of the following tips:

- Ensure unit is installed in a well-ventilated, dust-free environment.
- Unit is designed for indoor use only.
- Keep all liquids away from the device.
- Ensure environmental conditions meet factory specifications.
- Ensure unit is properly secured to a rack or shelf. Major shocks or jolts to the unit as a result of dropping it may cause damage to the sensitive electronics within the unit.
- Use the device in conjunction with an UPS if possible.
- Power down the unit before connecting and disconnecting accessories and peripherals.
- A factory recommended HDD should be used for this device.
- Improper use or replacement of the battery may result in hazard of explosion. Replace with the same or equivalent type only. Dispose of used batteries according to the instructions provided by the battery manufacturer.



## Product Key Features

### General

- PAL/NTSC adaptive video inputs.
- H.264 video compression with high reliability and superior definition.
- Encoding at up to WD1 (PAL: 960×576, NTSC: 960×480) resolution for DS-7204HWI-SV, DS-7200HWI-SH, DS-7200HVI-SV and DS-7300HWI-SH; and up to 4CIF resolution for DS-7200HVI-SH, DS-7200HFI-SH and DS-7300HFI-SH.
- Each channel supports dual-stream.
- Independent configuration for each channel, including resolution, frame rate, bit rate, image quality, etc.
- Input and output video quality is configurable.
- Normal and event recording parameters configurable per individual camera.
- Encoding for both audio/video composite stream and video stream; audio and video synchronization during composite stream encoding.
- Watermark technology.

### Local Monitoring

- Simultaneous HDMI/VGA and CVBS outputs.
- HDMI/VGA output at up to 1920×1080P resolution.
- 1/4/6/8/9/16-division live view is supported, and the display sequence of screens is adjustable.
- Live view screen can be switched in group, and manual switch and automatic cycle view is also provided, the interval of automatic cycle can be adjusted.
- Quick setting menu is provided for live view.
- The selected live view channel can be shielded.
- Motion detection, tamper-proof, video exception and video loss alarm functions.
- Privacy mask.
- Multiple PTZ protocols supported; setting and calling of PTZ preset, patrol and pattern.
- Zooming in by clicking the mouse and PTZ tracing by dragging mouse.

### HDD Management

- 1 SATA hard disk can be connected to DS-7200HVI-SH, DS-7200HVI-SV, DS-7204HFI-SH, DS-7204HWI-SV and DS-7204HWI-SH models, 2 SATA hard disks to DS-7208/7216HFI-SH and DS-7208/7216HWI-SH models, and 4 SATA hard disks to DS-7300HFI-SH and DS-7300HWI-SH; with a maximum of 4TB storage capacity for each disk.
- 8 network disks (8 NAS disks, or 7 NAS disks+1 IP SAN disk) can be connected.
- HDD group management.
- Support HDD standby function.
- HDD property: redundancy, read-only, read/write (R/W).
- HDD quota management; different capacity can be assigned to different channel.

### Recording and Playback

- Holiday recording schedule configuration.
- Normal and event video encoding parameters.
- Multiple recording types: manual, normal, motion, alarm, motion/alarm and motion & alarm.  
**Note:** The alarm, motion/alarm and motion & alarm recording types are provided for DS-7300HWI/HFI-SH models only.

- 8 recording time periods with separated recording types.
- Pre-record and post-record for motion detection for recording, and pre-record time for schedule and manual recording.
- Searching record files by event.
- Customization of tags, searching and playing back by tags.
- Locking and unlocking record files.
- Local redundant recording.
- Searching and playing back record files by channel number, recording type, start time, end time, etc.
- Smart search for the selected area in the video.
- Zooming in when playback.
- Playing reversely.
- Support pause, speed up, speed down, skip forward, and skip backward when playback, locating by dragging the mouse.
- 4/8/16-ch synchronous playback at up to 4CIF resolution for DS-7200HVI/HFI-SH and DS-7300HFI-SH, and up to WD1 resolution for DS-7204HWI-SV, DS-7200HWI-SH, DS-7200HVI-SV and DS-7300HWI-SH.

### Backup

- Export video data by USB, SATA or eSATA storage device.  
*Note:* The eSATA is supported by DS-7300HWI/HFI-SH models only.
- Export video clips when playback.
- Management and maintenance of backup devices.

### Alarm and Exception

- Configurable arming time of alarm input/output (for DS-7300HWI/HFI-SH).
- Alarm for video loss, motion detection, tampering, abnormal signal, video input/output standard mismatch, illegal login, network disconnected, IP confliction, abnormal record, HDD error, and HDD full, etc.
- Alarm event triggers full screen monitoring, audio alarm, notifying surveillance center and sending email.
- Automatic restore when system is abnormal.

### Other Local Functions

- Operable by mouse, or IR remote control.
- Three-level user management; admin user is allowed to create many operating accounts and define their operating permission, which includes the limit to access any channel.
- Operation, exceptions and log recording and searching.
- Import and export of device configuration information.

### Network Functions

- 1 self-adaptive 10M/100M network interface for DS-7200-SH/SV, and 1 self-adaptive 10M/100M/1000M network interface for DS-7300HWI/HFI-SH.
- IPv6 is supported.
- TCP/IP protocol, PPPoE, DHCP, DNS, DDNS, RTSP, NTP, SADP, SMTP, SNMP, UPnP™, NFS, and iSCSI are supported.
- TCP, UDP and RTP for unicast.
- Remote search, playback, download, locking and unlocking of the record files, and downloading files broken transfer resume.

- Remote parameters setup; remote import/export of device parameters.
- Remote viewing of the device status, system logs and alarm status.
- Remote locking and unlocking of control panel and mouse.
- Remote HDD formatting and program upgrading.
- Remote system restart.
- RS-232 and RS-485 transparent channel transmission.  
*Note:* RS-232 serial port is provided for DS-7300HWI/HFI-SH only.
- Alarm event and exception information can be sent to the remote host.
- Remotely start/stop recording.
- Upgrade by remote FTP server.
- Remote PTZ control.
- Two-way audio and voice broadcasting.
- Embedded WEB server.

**Development Scalability:**

- SDK for Windows and Linux system.
- Source code of application software for demo.
- Development support and training for application system.

# TABLE OF CONTENTS

Product Key Features .....	4
<b>CHAPTER 1.....</b>	<b>11</b>
<b>Introduction.....</b>	<b>11</b>
1.1 Front Panel.....	12
1.2 IR Remote Control Operations.....	15
1.3 USB Mouse Operation.....	17
1.4 Input Method Description .....	17
1.5 Rear Panel .....	18
1.6 Starting Up and Shutting Down the Device .....	20
<b>CHAPTER 2.....</b>	<b>21</b>
<b>Getting Started .....</b>	<b>21</b>
<b>CHAPTER 3.....</b>	<b>26</b>
<b>Live View.....</b>	<b>26</b>
3.1 Introduction of Live View .....	27
3.2 Operations in Live View Mode .....	28
3.2.1 Front Panel Operation .....	28
3.2.2 Using the Mouse in Live View .....	28
3.2.3 Using an Auxiliary Monitor .....	29
3.2.4 Main/Aux Output Switching.....	30
3.2.5 Quick Setting Toolbar in Live View Mode.....	30
3.3 Adjusting Live View Settings.....	33
3.4 Channel-zero Encoding.....	35
3.5 User Logout.....	36
<b>CHAPTER 4.....</b>	<b>37</b>
<b>PTZ Controls.....</b>	<b>37</b>
4.1 Configuring PTZ Settings .....	38
4.2 Setting PTZ Presets, Patrols & Patterns .....	38
4.2.1 Customizing Presets.....	38
4.2.2 Calling Presets.....	39
4.2.3 Customizing Patrols .....	40
4.2.4 Calling Patrols.....	42
4.2.5 Customizing Patterns .....	43
4.2.6 Calling Patterns .....	44
4.3 PTZ Control Toolbar .....	45
<b>CHAPTER 5.....</b>	<b>46</b>
<b>Record Settings.....</b>	<b>46</b>
5.1 Configuring Encoding Parameters .....	47
5.2 Configuring Record Schedule.....	50
5.3 Configuring Motion Detection Record .....	53
5.4 Configuring Alarm Triggered Record .....	55
5.5 Configuring Manual Record .....	58

5.6 Configuring Holiday Record.....	59
5.7 Configuring Redundant Record .....	61
5.8 Configuring HDD Group for Record .....	62
5.9 Files Protection .....	64
<b>CHAPTER 6.....</b>	<b>67</b>
<b>Playback.....</b>	<b>67</b>
6.1 Playing Back Record Files .....	68
6.1.1 Playing Back by Channel .....	68
6.1.2 Playing Back by Time .....	71
6.1.3 Playing Back by Normal Video Search.....	73
6.1.4 Playing Back by Event Search .....	76
6.1.5 Playing Back by Tag .....	80
6.1.6 Playing Back by System Log .....	84
6.2 Auxiliary Functions of Playback.....	86
6.2.1 Playing Back Frame by Frame .....	86
6.2.2 Smart Search .....	86
6.2.3 Digital Zoom .....	89
<b>CHAPTER 7.....</b>	<b>90</b>
<b>Backup .....</b>	<b>90</b>
7.1 Backing up Record Files .....	91
7.1.1 Quick Export .....	91
7.1.2 Backing up by Normal Video Search.....	93
7.1.3 Backing up by Event Search .....	96
7.1.4 Backing up Video Clips .....	99
7.2 Managing Backup Devices .....	101
<b>CHAPTER 8.....</b>	<b>105</b>
<b>Alarm Settings.....</b>	<b>105</b>
8.1 Setting Motion Detection .....	106
8.2 Setting Sensor Alarms .....	108
8.3 Detecting Video Loss .....	111
8.4 Detecting Video Tampering.....	112
8.5 Handling Exceptions .....	113
8.6 Setting Alarm Response Actions .....	114
8.7 Triggering or Clearing Alarm Output Manually.....	116
<b>CHAPTER 9.....</b>	<b>117</b>
<b>Network Settings .....</b>	<b>117</b>
9.1 Configuring General Settings.....	118
9.2 Configuring Advanced Settings .....	119
9.2.1 Configuring PPPoE Settings .....	119
9.2.2 Configuring DDNS .....	119
9.2.3 Configuring NTP Server .....	122
9.2.4 Configuring SNMP .....	123
9.2.5 Configuring UPnP™.....	124
9.2.6 Configuring Remote Alarm Host .....	125

9.2.7 Configuring Multicast .....	126
9.2.8 Configuring RTSP .....	126
9.2.9 Configuring Server and HTTP Ports .....	127
9.2.10 Configuring Email .....	127
9.3 Checking Network Traffic .....	130
9.4 Network Detection .....	131
9.4.1 Testing Network Delay and Packet Loss .....	131
9.4.2 Exporting Network Packet .....	131
9.4.3 Checking Network Status .....	132
9.4.4 Checking Network Statistics .....	134
<b>CHAPTER 10 .....</b>	<b>134</b>
<b>HDD Management .....</b>	<b>134</b>
10.1 Initializing HDDs .....	135
10.2 Managing Network HDD .....	137
10.3 Managing HDD Group .....	140
10.3.1 Setting HDD Groups .....	140
10.3.2 Setting HDD Property .....	141
10.4 Configuring Quota Mode .....	143
10.5 Checking HDD Status .....	145
10.6 Checking S.M.A.R.T. Information .....	146
10.7 Detecting Bad Sector .....	147
10.8 Configuring HDD Error Alarms .....	148
<b>CHAPTER 11 .....</b>	<b>149</b>
<b>Camera Settings .....</b>	<b>149</b>
11.1 Configuring OSD Settings .....	150
11.2 Configuring Privacy Mask .....	151
11.3 Configuring Video Parameters .....	152
<b>CHAPTER 12 .....</b>	<b>153</b>
<b>Device Management and Maintenance .....</b>	<b>153</b>
12.1 Viewing System Information .....	154
12.1.1 Viewing Device Information .....	154
12.1.2 Viewing Camera Information .....	154
12.1.3 Viewing Record Information .....	155
12.1.4 Viewing Network Information .....	155
12.1.5 Viewing HDD Information .....	156
12.2 Searching & Exporting Log Files .....	157
12.3 Importing/Exporting Configuration Files .....	159
12.4 Upgrading System .....	161
12.4.1 Upgrading by Local Backup Device .....	161
12.4.2 Upgrading by FTP .....	161
12.5 Restoring Default Settings .....	163
<b>CHAPTER 13 .....</b>	<b>164</b>
<b>Others .....</b>	<b>164</b>
13.1 Configuring General Settings .....	165

13.2 Configuring RS-232 Serial Port .....	165
13.3 Configuring DST Settings .....	167
13.4 Configuring More Settings.....	168
13.5 Managing User Accounts .....	169
13.5.1 Adding a User .....	169
13.5.2 Deleting a User.....	171
13.5.3 Editing a User.....	172
13.5.4 Changing Password of Admin.....	173
13.6 Logging out/Shutting down/Rebooting Device.....	175
<b>CHAPTER 14.....</b>	<b>176</b>
<b>Appendix.....</b>	<b>176</b>
Glossary .....	177
FAQ.....	178

# **C H A P T E R 1**

## **Introduction**



## 1.1 Front Panel

The front panel of DS-7200-SH/SV series DVR is shown in Figure 1.1:



Figure 1.1 Front Panel of DS-7200-SH/SV

Table 1.1 Description of Control Panel Buttons

No.	Name	Function Description
1	<b>POWER</b>	POWER indicator turns green when DVR is powered up.
2	<b>STATUS</b>	STATUS indicator lights in red when HDD is reading/writing.
3	<b>Tx/Rx</b>	Tx/Rx indicator blinks green when network connection is functioning properly.
4	<b>USB Interface</b>	Connects USB mouse or USB flash memory devices.
5	<b>IR Receiver</b>	Receiver for IR remote.

The front panel of DS-7300-SH is shown below:



Figure 1.2 Front Panel of DS-7300-SH

Table 1.2 Description of Control Panel Buttons

No.	Name	Function Description
1	<b>POWER ON/OFF</b>	Power on/off switch.
2	<b>IR Receiver</b>	Receiver for IR remote control.
3	<b>USB</b>	Connect to USB mouse or USB flash memory devices.
4	<b>DVD-ROM</b>	Slot for DVD-ROM.
5	<b>POWER</b>	Power indicator lights in green when DVR is powered up.
	<b>READY</b>	Ready indicator is normally green, indicating that the DVR is functioning properly.
	<b>STATUS</b>	Indicator turns green when DVR is controlled by an IR remote control with the address from 1~254; Indicator turns red when the SHIFT button is used; Indicator does not light when the DVR is controlled by a keyboard or by the IR remote control with the address of 255; Indicator turns green when the DVR is controlled by IR remote control (with the address from 1~254) and keyboard at the same time, and the SHIFT button is not used;

6		Indicator turns orange : (a) when the DVR is controlled by IR remote control (with the address from 1~254) and keyboard at the same time and the SHIFT button is used as well; (b) when the DVR is controlled by IR remote control (with the address from 1~254) and the SHIFT button is used.
	<b>ALARM</b>	Alarm indicator turns red when a sensor alarm is detected.
	<b>HDD</b>	HDD indicator blinks in red when data is being read from or written to HDD.
	<b>Tx/Rx</b>	TX/RX indicator blinks in green when network connection is functioning properly.
	<b>1/MENU</b>	Enter numeral "1"; Access the main menu interface.
	<b>2ABC/F1</b>	Enter numeral "2"; Enter letters "ABC"; The F1 button can be used to select all items on the list; In PTZ Control mode, the F1 button can be used to zoom out (zoom-) the PTZ camera; In live view or playback mode, the F1 button can be used to switch between main and spot video output.
	<b>3DEF/F2</b>	Enter numeral "3"; Enter letters "DEF"; In PTZ Control mode, the F1 button can be used to zoom in (zoom+) the PTZ camera; The F2 button can be used to cycle through tab pages.
	<b>4GHI/ESC</b>	Enter numeral "4"; Enter letters "GHI"; Exit and back to the previous menu.
	<b>5JKL/EDIT</b>	Enter numeral "5"; Enter letters "JKL"; Delete characters before cursor; Select the checkbox and ON/OFF switch; Start/stop record clipping in playback.
	<b>SHIFT</b>	Switch of compound keys between the numeric/letter input and functional control.
	<b>6MNO/PLAY</b>	Enter numeral "6"; Enter letters "MNO"; In Playback mode, it is used for direct access to playback interface.
	<b>7PQRS/REC</b>	Enter numeral "7"; Enter letters "PQRS"; Manual record, for direct access to manual record interface; manually enable/disable record.
	<b>8TUV/PTZ</b>	Enter numeral "8"; Enter letters "TUV"; Access PTZ control interface.
	<b>9WXYZ/PREV</b>	Enter numeral "9"; Enter letters "WXYZ"; Multi-camera display in live view; In Playback mode or Menu→Playback→Tag playback interface, this button can be used to delete the selected tag.
	<b>0/A</b>	Enter numeral "0"; Switch between input methods (upper and lowercase alphabet, symbols and numeric input). In Playback mode, this button can be used to add the default tag.
7	<b>DIRECTION</b>	The DIRECTION buttons are used to navigate between different fields and items in menus. In Playback mode, the Up and Down button is used to speed up and slow down recorded video. In All-day Playback mode, the Left/Right button can be used to select the recorded video of next/previous day; in Playback by Normal Video Search, the Left/Right button can be used to select the next/previous recorded file. In Live View mode, the directional buttons can be used to cycle through channels. In PTZ control mode, it can control the movement of the PTZ camera.
	<b>ENTER</b>	Confirm selection in any of the menu modes. It can also be used to tick checkbox

		<p>fields.</p> <p>In Playback mode, it can be used to play or pause the video.</p> <p>In Single-frame Playback mode, pressing the ENTER button will advance the video by a single frame.</p> <p>In Auto-switch mode, it can be used to stop /start auto switch.</p>
8	<b>JOG SHUTTLE Control</b>	<p>Move the active selection in a menu. The inner ring will move the selection up and down; the outer ring will move it left and right.</p> <p>In Playback mode, the inner ring is used to jump 30s forward/backward in video files. The outer ring can be used to speed up/slow down the video.</p> <p>In Live View mode, it can be used to cycle through different channels.</p> <p>In PTZ control mode, it can control the movement of the PTZ camera.</p>

## 1.2 IR Remote Control Operations

The device may also be controlled with the included IR remote control, shown in Figure 1.3.

**Note:** Batteries (2×AAA) must be installed before operation.




Figure 1.3 Remote Control

Table 1.3 Description of the IR Remote Control Buttons

No.	Name	Description
1	<b>POWER</b>	Power on/off the device.
2	<b>DEV</b>	Enables/Disables Remote Control.
3	<b>Alphanumeric Buttons:</b>	Switching to the corresponding channel in Live view or PTZ Control mode. Inputting numbers and characters in Edit mode. Switching between different channels in All-day Playback mode.
4	<b>EDIT Button</b>	Editing text fields. When editing text fields, it will also function as a Backspace button to delete the character in front of the cursor. On checkbox fields, pressing the EDIT button will <i>tick</i> the checkbox. In Playback mode, it can be used to generate video clips for backup.
5	<b>A Button</b>	Switching between input methods (upper and lowercase alphabet, symbols and numeric input).
6	<b>REC Button</b>	Entering the Manual Record settings menu.

No.	Name	Description
		In PTZ control settings, press the REC button and then you can call a PTZ preset by pressing Numeric button.
7	<b>PLAY Button</b>	Entering the All-day Playback menu.
8	<b>INFO Button</b>	Reserved.
9	<b>VOIP/MON Button</b>	Selecting all items on the list; In live view or playback mode, it can be used to switch between main and auxiliary video output.
10	<b>MENU Button</b>	Back to the Main menu (after successful login).
11	<b>PREV Button</b>	Switching between single screen and multi-screen mode.
12	<b>DIRECTION/ENTER Buttons</b>	Navigating between different fields and items in menus. In Playback mode, the Up and Down button are used to speed up and slow down the playing of recorded video. The Left and Right button will select the recorded video of 30 reverse and 30s forward. In live view mode, these buttons can be used to cycle through channels.
13	<b>PTZ Button</b>	Enter the PTZ Control mode.
14	<b>ESC Button</b>	Back to the previous menu Pressing for arming/disarming the DVR in Live View mode.
15	<b>RESERVED</b>	Reserved.
16	<b>F1 Button</b>	Selecting all items on the list when used in a list field. In PTZ Control mode, it will turn on/off PTZ light.
17	<b>PTZ Control Buttons</b>	Adjusting the iris, focus and zoom of a PTZ camera.
18	<b>F2 Button</b>	Cycle through tab pages.

**Troubleshooting Remote Control:**

**Note:** Make sure you have installed batteries properly in the remote control. And you have to aim the remote control at the IR receiver on the front panel.

If there is no response after you press any button on the remote, follow the procedure below to troubleshoot.

**Steps:**

1. Go to Menu > Configuration > General > More Settings by operating the mouse.
2. Check and remember the device No. The default No. is 255. This device No. is valid for all the IR remote controls.
3. Press the DEV button on the remote control.
4. Enter the device No. from step 2.
5. Press the ENTER button on the remote.

If the remote control is operating properly, but there is still no response from the remote, please check the following:

1. Batteries are installed correctly and the polarities of the batteries are not reversed.
2. Batteries are fresh and not out of charge.
3. IR receiver is not obstructed.

If the remote still can't function properly, please change a remote and try again, or contact the device provider.

## 1.3 USB Mouse Operation

A regular 3-button (Left/Right/Scroll-wheel) USB mouse can also be used with this device. To use a USB mouse:

1. Plug USB mouse into one of the USB interfaces on the front panel of the device.
2. The mouse should automatically be detected. If in a rare case that the mouse is not detected, the possible reason may be that the two devices are not compatible, please refer to the recommended device list from your provider.

The operation of the mouse:

Table 1.4 Description of the Mouse Control

Name	Action	Description
Left-Click	Single-Click	Live view: Select channel and show the quick set menu. Menu: Select and enter.
	Double-Click	Live view: Switch single-screen and multi-screen.
	Click and Drag	PTZ control: pan, tilt and zoom. Tamper-proof, privacy mask and motion detection: Select target area. Digital zoom-in: Drag and select target area. Live view: Drag channel/time bar.
Right-Click	Single-Click	Live view: Show menu. Menu: Exit current menu to upper level menu.
Scroll-Wheel	Scrolling up	Live view: Previous screen. Right-click Menu: Previous item.
	Scrolling down	Live view: Next screen. Right-click Menu: Next item.

## 1.4 Input Method Description



Figure 1.4 Soft Keyboard

Description of the buttons on the soft keyboard:

Table 1.5 Description of the Soft Keyboard Icons

Icons	Description	Icons	Description
	English		Capital English
	Numbers		Symbols
	Lowercase/Uppercase		Backspace
	Space		Enter
	Exit		

## 1.5 Rear Panel

The rear panels of DS-7200-SH/SV series DVR are shown in Figure 1.5, Figure 1.6 and Figure 1.7.



Figure 1.5 Rear Panel of DS-7204HVI/HFI/HWI-SH, DS-7204HVI-SV and DS-7204HWI-SV




Figure 1.6 Rear Panel of DS-7216HVI-SH and DS-7216HVI-SV

**Note:** The rear panel of DS-7208HVI-SH and DS-7208HVI-SV provides 8 video input interfaces.




Figure 1.7 Rear Panel of DS-7216HFI-SH and DS-7216HWI-SH

**Note:** The rear panel of DS-7208HFI-SH and DS-7208HWI-SH provides 8 video input interfaces.

Table 1.6 Description of Rear Panel

No.	Item	Description
1	<b>VIDEO IN</b>	BNC connector for analog video input.
2	<b>VIDEO OUT</b>	BNC connector for video output.
3	<b>USB Interface</b>	Connects USB mouse or USB flash memory devices.
4	<b>HDMI</b>	HDMI video output.
5	<b>VGA</b>	DB15 connector for VGA output. Display local video output and menu.
6	<b>AUDIO IN</b>	RCA connector for audio input.
7	<b>AUDIO OUT</b>	RCA connector for audio output.
8	<b>LAN Interface</b>	Connector for LAN (Local Area Network).
9	<b>RS-485 Interface</b>	Connector for RS-485 devices. Connect the D+ and D- terminals to T+ and T- of PTZ receiver respectively.
10	<b>12V</b>	12VDC power supply.
11	<b>POWER</b>	Switch for turning on/off the device.
12	<b>GND</b>	Ground(needs to be connected when DVR starts up).

The rear panels of DS-7300HFI-SH and DS-7300HWI-SH DVR are shown in Figure 1.8, Figure 1.9 and Figure 1.10




Figure 1.8 Rear Panel of DS-7304HFI-SH and DS-7304HWI-SH




Figure 1.9 Rear Panel of DS-7308HFI-SH and DS-7308HWI-SH




Figure 1.10 Rear Panel of DS-7316HFI-SH and DS-7316HWI-SH

Table 1.7 Description of Rear Panel

No.	Item	Description
1	<b>VIDEO IN</b>	BNC connector for analog video input.
2	<b>MAIN VIDEO OUT</b>	BNC connector for video output.
	<b>SPOT VIDEO OUT</b>	BNC connector for spot video output.
3	<b>HDMI</b>	HDMI video output.
4	<b>USB Interface</b>	Connects USB mouse or USB flash memory devices.
5	<b>RS-232</b>	Connector for RS-232 devices.
6	<b>VGA</b>	DB15 connector for VGA output. Display local video output and menu.
7	<b>AUDIO IN</b>	RCA connector for audio input.
8	<b>AUDIO OUT</b>	RCA connector for audio output.
9	<b>LAN Interface</b>	RJ45 10M / 100M / 1000M Ethernet interface.
10	<b>RS-485 Interface</b>	Connector for RS-485 devices. Connect the D+ and D- terminals to R+ and R- terminals of PTZ receiver respectively.
11	<b>Alarm In/Out</b>	Connector for alarm input/output.
12	<b>eSATA</b>	Connects external SATA HDD, DVD-R/W.
13	<b>110~240VAC</b>	12VDC power supply.
14	<b>POWER</b>	Switch for turning on/off the device.
15	<b>GND</b>	Ground(needs to be connected when DVR starts up)



## 1.6 Starting Up and Shutting Down the Device

### *Purpose:*

Proper startup and shutdown procedures are crucial to expanding the life of the device.

### *Before you start:*

Check that the voltage of the extra power supply is the same with the device's requirement, and the ground connection is working properly.

### **Starting up the device:**

#### *Steps:*

1. Check the power supply is plugged into an electrical outlet. It is **HIGHLY** recommended that an Uninterruptible Power Supply (UPS) be used in conjunction with the device.
2. Press the **POWER** button on the rear panel. The Power indicator LED should turn green indicating that the unit begins to start up.

### **Shutting down the device:**

#### *Steps:*

1. Enter the Shutdown menu.  
Menu > Shutdown




Figure 1.11 Shutdown Menu

2. Click the **Shutdown** button to enter the following dialog box:



Figure 1.12 Dialog Box for Shutdown

3. Click the **Yes** button. The following message box pops up:




Figure 1.13 Message Box for Power Off

4. Turn off the power switch on the rear panel of DVR.

### **Rebooting the device**

In the Shutdown menu (Figure 1.11), you can also click **Reboot** to reboot the device.

# **C H A P T E R 2**

## **Getting Started**

The Setup Wizard can walk you through some important settings of the device. By default, the Setup Wizard starts once the device has loaded.

Operating the Setup Wizard:

1. Select the system resolution from the drop-down menu. The default resolution is 1280×1024/60Hz.  
Click **Apply** to save the resolution settings.




Figure 2.1 Start Wizard Interface

---

2. Check the checkbox to enable Setup Wizard when device starts. Click **Next** to continue the setup wizard.

You can also click **Cancel** to exit the Setup Wizard, or use the Setup Wizard next time by leaving the "Start wizard when DVR starts?" checkbox checked and exit.





Figure 2.2 Start Wizard Interface

---

3. Click **Next** button on the Wizard window to enter the **Login** window, as shown in Figure 2.3.
  - 1) Enter the admin password. By default, the password is 12345.
  - 2) To change the admin password, check the **New Admin Password** checkbox. Enter the new password and confirm the password in the given fields.



Wizard	
Admin Password	*****
New Admin Password	<input checked="" type="checkbox"/>
New Password	*****
Confirm	*****
<div>Previous   Next   Cancel</div>	

Figure 2.3 Login Window


- Click the **Next** button to enter the **Date and Time** settings window, as shown in Figure 2.4.  
Set the time zone, date format, system date and system time.



Wizard	
Time Zone	(GMT+08:00) Beijing, Urumqi, Singapore
Date Format	MM-DD-YYYY
System Date	06-24-2011
System Time	16:18:12
<div>Previous   Next   Cancel</div>	

Figure 2.4 Date and Time Settings

- Click **Next** button which takes you back to the **Network** Setup Wizard window, as shown in Figure 2.5.  
Set the network parameters, including the NIC type, IPv4 address, IPv4 subnet mask, default gateway, etc. You can enable the DHCP to automatically obtain an IP address and other network settings from that server.



The image shows a 'Wizard' window for network configuration. It has a red title bar with the word 'Wizard' in white. Below the title bar, there are several fields for configuration. The 'NIC Type' is set to '10M/100M Self-adaptive'. The 'Enable DHCP' checkbox is unchecked. The 'IPv4 Address' is '172.16.1.65', the 'IPv4 Subnet Mask' is '255.255.255.0', and the 'IPv4 Default Gateway' is '172.16.1.1'. There are also fields for 'Preferred DNS Server' and 'Alternate DNS Server', both of which are empty. At the bottom of the window, there are three buttons: 'Previous', 'Next', and 'Cancel'.


Field	Value
NIC Type	10M/100M Self-adaptive
Enable DHCP	<input type="checkbox"/>
IPv4 Address	172.16.1.65
IPv4 Subnet Mask	255.255.255.0
IPv4 Default Gateway	172.16.1.1
Preferred DNS Server	
Alternate DNS Server	

Figure 2.5 Network Configuration

**Note:** The DS-7200-SH/SV models provide one 10M/100Mbps self-adaptive network interface, and the DS-7300HWI/HFI-SH models provide one 10M/100M/1000Mbps self-adaptive network interface.

6. Click **Next** button to enter the **HDD Management** window, shown in Figure 2.6.

To initialize the HDD, click the **Init** button. Initialization removes all the data saved in the HDD.



The image shows an 'HDD Management' window within a 'Wizard'. It has a red title bar with the word 'Wizard' in white. Below the title bar, there is a table with columns: 'Label', 'Capacity', 'Status', 'Property', 'Type', and 'Free Space'. The table contains one row with the following data: '1', '76,319MB', 'Normal', 'R/W', 'Local', and '50,176MB'. Below the table, there is an 'Init' button. At the bottom of the window, there are three buttons: 'Previous', 'Next', and 'Cancel'.

Label	Capacity	Status	Property	Type	Free Space
1	76,319MB	Normal	R/W	Local	50,176MB

Figure 2.6 HDD Management

7. Click **Next** button to enter the **Record Settings** window, as shown in Figure 2.7.

- 1) Select the camera to configure.
- 2) Check the checkbox to enable **Start Recording**.
- 3) Select the recording mode to Normal or Motion Detection.



Figure 2.7 Record Settings

- 
- 4) Click **Copy** to copy the record settings of the current camera to other camera (s) if needed, as shown in Figure 2.8.



Figure 2.8 Copy Record Settings

- 
- 5) Click **OK** to return to the **Record Settings** window.
8. Click **OK** to complete the startup Setup Wizard.

# **C H A P T E R 3**

## **Live View**




## 3.1 Introduction of Live View

Live view shows you the video image getting from each camera in real time. The device automatically enters Live View mode when powered on. It is also at the very top of the menu hierarchy, thus pressing the ESC many times (depending on which menu you're on) brings you to the Live View mode.

### Live View Icons

In the live view mode, there are icons at the right top of the screen for each channel, showing the status of the record and alarm in the channel, so that you can know whether the channel is recorded, or whether there are alarms occur as soon as possible.

Table 3.1 Description of Live View Icons

Icons	Description
	Alarm (video loss, tampering, motion detection or sensor alarm)
	Record (manual record, schedule record, motion detection or alarm triggered record)
	Alarm & Record



## 3.2 Operations in Live View Mode

In live view mode, the following functions can be realized:

- **Single Screen:** showing only one screen on the monitor.
- **Multi-screen:** showing multiple screens on the monitor simultaneously.
- **Auto-switch:** the screen is auto switched to the next one. And you must set the dwell time for each screen on the configuration menu before enabling the auto-switch.  
Menu>Configuration>Live View>Dwell Time.
- **All-day Playback:** play back the recorded videos for current day.
- **Start Recording:** start all-day normal recording or motion detection recording for all channels.
- **Aux/Main output switch:** the DVR will check the connection of the output interfaces to define the main and auxiliary output interfaces. When both HDMI and VGA are connected, or either one is connected, it is used as the auxiliary video output for live view, playback, recording and PTZ controls; When both HDMI and VGA are not connected, it is used as the main video output for live view playback, recording, PTZ control and menu operations.

When the aux output is enabled, you can do some basic operation on the live view mode for the Aux output, while no operation is allowed for the main output.

### 3.2.1 Front Panel Operation

For the DS-7300HWI-SH and DS-7300HFI-SH models, you can operate the front panel buttons to realize the following functions in live view:

Table 3.2 Front Panel Operation in Live View

Functions	Front Panel Operation
Show single screen	Press the corresponding Alphanumeric button. E.g. Press 2 to display only the screen for channel 2.
Show multi-screen	Press the PREV/FOCUS- button.
Manually switch screens	Next screen: right direction button. Previous screen: left direction button.
Auto-switch	Press <b>Enter</b> button.
All-day playback	Press <b>Play</b> button.
Switch main and aux output	Press <b>F1</b> button and <b>Enter</b> button.

### 3.2.2 Using the Mouse in Live View

In the live view mode, use the mouse to right-click on the window to access the following menu:




Figure 3.1 Right-click Menu

Table 3.3 Mouse Operation in Live View

Name	Description
Menu	Enter the main menu of the system by right-clicking the mouse.
Single Screen	Switch to the single full screen by choosing channel number from the dropdown list.
Multi-screen	Adjust the screen layout by choosing from the dropdown list.
Previous Screen	Switch to the previous screen.
Next Screen	Switch to the next screen.
Start/Stop Auto-switch	Enable/disable the auto-switch of the screens. <b>Note:</b> The <i>dwelling time</i> of the live view configuration must be set before using <b>Start Auto-switch</b> .
Start Recording	Start all-day normal recording or motion detection recording for all channels.
Quick Set	Set the video output mode to Standard, Bright, Gentle or Vivid.
All-day Playback	Play back the video of the selected channel.
Aux Monitor	Switch to the auxiliary output mode and the operation for the main output is disabled. <b>Note:</b> If you enter Aux monitor mode and the Aux monitor is not connected, the mouse operation is disabled; you need to switch back to the Main output with the <b>VOIP/MON</b> button on IR remote control and then press the Enter button.

**Note:** If the corresponding camera supports intelligent function, the Reboot Intelligence option is included when right-clicking mouse on this camera.

### 3.2.3 Using an Auxiliary Monitor

Certain features of the Live View are also available while in an Aux monitor. These features include:

- **Single Screen:** Switch to the single full screen by choosing channel number from the dropdown list.
- **Multi-screen:** Adjust the screen layout by choosing from the dropdown list.
- **Previous Screen:** Switch to the previous screen.
- **Next Screen:** Switch to the next screen.
- **Quick Set:** Set the video output mode to Standard, Bright, Gentle or Vivid.
- **Menu Output Mode:** Select the menu output mode to HDMI/VGA, Main CVBS or Auto.
- **Main Monitor:** Switch to the Main Output mode and the operation for the auxiliary output is disabled.

**Note:** In the live view mode of the main output monitor, the menu operation is not available while Aux output mode is enabled.

### 3.2.4 Main/Aux Output Switching

When the HDMI/VGA output is configured as the main output, you can perform the following operation to switch to CVBS output as the main output.

**Steps:**

1. Use the mouse wheel to double-click on the HDMI/VGA output screen, and the following message box pops up:




Figure 3.2 Switch Main and Aux Output

2. Use the mouse wheel to double-click on the screen again to switch to the Aux output, or click **Cancel** to cancel the operation.
3. Select the **Menu Output Mode** to **Main CVBS** from the right-click menu on the CVBS output monitor.




Figure 3.3 Right-click Menu on CVBS Output Monitor

4. On the pop-up message box, click **Yes** to restart the device to enable the CVBS output as the main output.

**Note:** You can select the Menu Output Mode under Menu>Configuration>More Settings to Auto or HDMI/VGA and then restart the device to switch the main output back to HDMI/VGA output.








### 3.2.5 Quick Setting Toolbar in Live View Mode

On the screen of each channel, there is a quick setting toolbar which shows when you right-click mouse on the camera.



Figure 3.4 Quick Settings Toolbar

Table 3.4 Description of Quick Setting Toolbar Icons

Icons	Description	Icons	Description	Icons	Description
	Enable Manual Record		Instant Playback		Mute/Audio on
	PTZ Control		Digital Zoom		Image Settings
	Close				

### Instant Playback



Instant Playback only shows the record in last five minutes. If no record is found, it means there is no record during the last five minutes.

### Digital Zoom



Digital Zoom can zoom in the selected area to the full screen. You can left-click and draw to select the area for zooming in, as shown in Figure 3.3.




Figure 3.5 Digital Zoom

### Image Settings



Image Settings icon can be selected to enter the Image Settings menu.

#### Steps:

- Set the period of a day for configuring independent image parameters so as to satisfy different light conditions, e.g., daylight and night time. Two periods can be configured. When you have configured Period 1, the Period 2 is remained as the *Other Time*.
- Select the mode from the drop-down menu according to different light conditions.  
Four modes are selectable:
  - Standard:** in general lighting conditions (default).
  - Indoor:** the image is relatively smoother.

- **Dim Light:** the image is smoother than the other three modes.
- **Outdoor:** the image is relatively clearer and sharper. The degree of contrast and saturation is high.



Figure 3.6 Image Settings

- Adjust the image parameters including the brightness, contrast, saturation, hue, sharpness level and denoising level by moving the sliding bar or increasing/decreasing the value.  
**Note:** The adjustable value range is 0~ 255 for the brightness, contrast, saturation and hue, 0~ 15 for the sharpness level and 0~5 for the denoising level.
- Copy image parameters.
  - If you want to copy the image parameters of the current camera to other camera (s), click the **Copy** button to enter the **Copy to** interface:




Figure 3.7 Copy Image Settings to Other Camera (s)

- Select the camera (s) to be configured with the image settings. You can also click the checkbox of Analog to select all cameras.
- Click the **OK** button to finish the Copy settings.

**Note:** You can click the **Restore** button to restore the current image settings to default parameters.

## 3.3 Adjusting Live View Settings

### Purpose:

Live View settings can be customized according to different needs. You can configure the output interface, dwell time for screen to be shown, mute or turning on the audio, the screen number for each channel, etc.

### Steps:

1. Enter the Live View Settings interface.

Menu> Configuration> Live View




Figure 3.8 Live View-General

The settings available in this menu include:

- **Video Output Interface:** Select the output to configure the settings for. Two output interfaces are selectable: VGA/HDMI and Main CVBS.
- **Live View Mode:** Select different window-division mode from the drop-down list.
- **Dwell Time:** The time in seconds to *dwell* between switching of channels when enabling auto-switch in Live View.
- **Enable Audio Output:** Enable/disable audio output for the selected video output.

### Notes:

1. When the VGA/HDMI output interface is used as the main video output and the **Audio Output** for the VGA/HDMI output interface is enabled, the VGA/HDMI audio and AUDIO OUT can be used for live view, playback and two-way audio.
2. When the VGA/HDMI output is used as the main video output and the **Audio Output** for the VGA/HDMI output interface is disabled, the VGA/HDMI output provides no audio and the AUDIO OUT is used for two-way audio.
3. When the CVBS output is used as the main video output, the VGA/HDMI audio is provided for Aux video output in live view, and the AUDIO OUT is used as the main video output (for live view, playback or two-way audio).

- **Event Output:** Select the output to show event video.
- **Full Screen Monitoring Dwell Time:** The time in seconds to show alarm event screen.

2. Setting Camera Order








Figure 3.9 Live View- Camera Order

To set the camera order:

- 1) Click the **View** tab to enter the camera order settings interface.
  - 2) Select an output interface and select a screen layout.
  - 3) Click to select a screen in the right region and double-click to select a channel in the left region.  
Thus the selected channel will be displayed in the corresponding screen.
- Note:** X means the channel will not be displayed.
- 4) You can click  to start live view of all channels and click  to stop live view of all channels.  
Click  or  to go to the previous or next page.
  - 5) Click the **Apply** button to save the setting.

## 3.4 Channel-zero Encoding

### *Purpose:*

Sometimes you need to get a remote view of many channels in real time from web browser or CMS (Client Management System) software, in order to decrease the bandwidth requirement without affecting the image quality, channel-zero encoding is supported as an option for you.

### *Steps:*

1. Enter the **Live View** Settings interface.  
Menu> Configuration> Live View
2. Select the **Channel-Zero Encoding** tab.




Figure 3.10 Live View- Channel-Zero Encoding

3. Check the checkbox after **Enable Channel-Zero Encoding**.
4. Configure the Frame Rate, Max. Bitrate Mode and Max. Bitrate.

After you set the Channel-Zero encoding, you can get a view in the remote client or IE browser of all the channels in one screen.



## 3.5 User Logout

### *Purpose:*

After logging out, the monitor turns to the live view mode and if you want to do some operation, you need to enter user name and password to log in again.

### *Steps:*

1. Enter the Shutdown menu.

Menu>Shutdown




Figure 3.11 Shutdown

2. Click **Logout**.

**Note:** After you have logged out the system, menu operation on the screen is invalid. It is required a user name and password to login the system.

# **C H A P T E R 4**

## **PTZ Controls**

## 4.1 Configuring PTZ Settings

### *Purpose:*

Follow the procedure to set the parameters for PTZ. The configuring of the PTZ parameters should be done before you control the PTZ camera.

### *Before you start:*

Check that the PTZ and the device are connected properly through RS-485 interface.

### *Steps:*

1. Enter the PTZ Settings interface.

Menu>Camera>PTZ>General

General	More Settings
Camera	Analog 1
Baud Rate	9600
Data Bit	8
Stop Bit	1
Parity	None
Flow Ctrl	None
PTZ Protocol	
Address	0
Address range: 0~255	

Figure 4.1 PTZ- General

2. Choose the camera for PTZ setting in the **Camera** dropdown list.

3. Enter the parameters of the PTZ camera.

**Note:** All the parameters should be exactly the same as the PTZ camera parameters. Only PTZ Protocol can be set for network cameras.

**Example:** If the PTZ camera has a Baud rate as 115200, you should input 115200 in the Baud rate field.

4. Click **Copy** if you want to configure same settings to other PTZ cameras.

5. Click **Apply** button to save the settings.

## 4.2 Setting PTZ Presets, Patrols & Patterns

### *Before you start:*

Please make sure that the presets, patrols and patterns should be supported by PTZ protocols.

### 4.2.1 Customizing Presets

#### *Purpose:*

Follow the steps to set the Preset location which you want the PTZ camera to point to when an event takes place.

#### *Steps:*

1. Enter the PTZ Control interface.

Menu>Camera>PTZ>More Settings




Figure 4.2 PTZ- More Settings

2. Use the directional button to wheel the camera to the location where you want to set preset.
3. Click the round icon before **Save Preset**.
4. Click the preset number to save the preset.

Repeat the steps2-4 to save more presets. If the number of the presets you want to save is more than 17, you can click [...] and choose the available numbers.



Figure 4.3 More Presets

## 4.2.2 Calling Presets

### *Purpose:*

This feature enables the camera to point to a specified position such as a window when an event takes place.

### **Call preset in the PTZ setting interface:**

#### *Steps:*

1. Enter the PTZ Control interface.  
Menu>Camera>PTZ>More Settings
2. Check the round icon before **Call Preset**.




Figure 4.4 PTZ- Call Preset

3. Choose the preset number.

#### Call preset in live view mode:

##### Steps:


1. Click the PTZ Control icon  in the quick setting bar to enter the PTZ setting menu in live view mode.



Figure 4.5 PTZ Toolbar


2. Choose **Camera** in the list on the menu.
3. Choose preset in the **Preset** list.

## 4.2.3 Customizing Patrols

#### Purpose:

Patrols can be set to move the PTZ to different key points and have it stay there for a set duration before moving on to the next key point. The key points are corresponding to the presets. The presets can be set following the steps above in *Customizing Presets*.

**Steps:**

1. Enter the PTZ Control interface.  
Menu>Camera>PTZ>More Settings
2. Select patrol number.
3. Select the  under Patrol option box to add key points for the patrol.




Figure 4.6 PTZ- Add Key Point

4. Configure key point parameters, such as the key point No., duration of staying for one key point and speed of patrol. The key point is corresponding to the preset. The **Key Point No.** determines the order at which the PTZ will follow while cycling through the patrol. The **Duration** refers to the time span to stay at the corresponding key point. The **Speed** defines the speed at which the PTZ will move from one key point to the next.




Figure 4.7 Key point Configuration

5. Click **OK** to save the key point to the patrol.

Repeat the above steps to add more key points.


You can also delete all the key points by clicking the trash icon .



Figure 4.8 KeyPoints Deletion

## 4.2.4 Calling Patrols

### *Purpose:*

Calling a patrol makes the PTZ to move according the predefined patrol path.

### **Calling patrol in the PTZ setting interface:**

#### *Steps:*

1. In the PTZ setting interface.  
Menu> Camera> PTZ> More Settings
2. Select the patrol number, and then click to call the patrol.
3. Click to stop it.




Figure 4.9 Calling Patrol

### **Calling preset in live view mode:**

#### *Steps:*


1. Press PTZ control on the IR remote, or click PTZ Control icon  on the quick setting toolbar, to show the PTZ control toolbar.
2. Choose **Patrol** on the control bar.
3. Click the patrol you want to call.



Figure 4.10 PTZ Toolbar- Patrol

## 4.2.5 Customizing Patterns

### *Purpose:*

Patterns can be set by recording the movement of the PTZ. You can call the pattern to make the PTZ movement according to the predefined path.

### *Steps:*

1. Enter the PTZ Control interface.  
Menu>Camera>PTZ>More Settings
2. Choose pattern number in the option box.






Figure 4.11 PTZ- Pattern

3. Click , and use your mouse to drag the image or click the eight directional buttons in the control box



under the image to move the PTZ camera.

The movement of the PTZ is recorded as the pattern.

4. Click  to save the pattern.

Repeat the above steps to save more patterns.



## 4.2.6 Calling Patterns

### *Purpose:*

Follow the procedure to move the PTZ camera according to the predefined patterns.

### Calling pattern in the PTZ setting interface

#### *Steps:*

1. Enter the PTZ Control interface.
2. Select the pattern number.
3. Click , then the PTZ moves according to the pattern. Click  to stop it.




Figure 4.12 PTZ- Calling Pattern

### Call pattern in live view mode.

#### *Steps:*



1. In the live view mode, press PTZ control on the IR remote control, or click PTZ Control icon  on the quick setting toolbar.
2. And then choose **Pattern** on the control bar.
3. Double click the pattern number you want to call, or you can select the pattern number and click  to call the pattern.



Figure 4.13 PTZ Toolbar- Pattern

## 4.3 PTZ Control Toolbar

In the Live View mode, you can press the PTZ Control button on the IR remote control, or choose the PTZ




















Control icon  to enter the PTZ toolbar.



Figure 4.14 PTZ Toolbar

Table 4.1 Description of the PTZ toolbar icons

Icon	Description	Icon	Description	Icon	Description
	Direction button and the auto-cycle button		Zoom+, Focus+, Iris+		Zoom-, Focus-, Iris-
	The speed of the PTZ movement		Light on/off		Wiper on/off
	3D-Zoom		Image Centralization		Preset
	Patrol		Pattern		Menu
	Previous item		Next item		Start pattern/patrol
	Stop the patrol or pattern movement		Minimize windows		Exit

# **C H A P T E R 5**

## **Record Settings**

## 5.1 Configuring Encoding Parameters

### Purpose:

By configuring the encoding parameters you can define the transmission stream type, the resolution and so on.

### Before you start:

1. Make sure that the HDD has already been installed. If not, please install a HDD and initialize it.  
(Menu>HDD>General)




Figure 5.1 HDD- General

2. Check the storage mode of the HDD
  - 1) Click **Advanced** to check the storage mode of the HDD.
  - 2) If the HDD mode is *Quota*, please set the maximum record capacity and maximum picture capacity. For detailed information, see *Chapter 10.5 Configuring Quota Mode*.
  - 3) If the HDD mode is *Group*, you should set the HDD group. For detailed information, see *Chapter 5.9 Configuring HDD Group for Recording*.




Figure 5.2 HDD- Advanced

### Steps:

1. Enter the Record settings interface to configure the encoding parameters:  
Menu>Record>Encoding

Record Substream		
Camera	Analog 1	
Encoding Parameters	Main Stream(Normal)	Main Stream(Event)
Stream Type	Video & Audio	Video & Audio
Resolution	WD1	WD1
Bitrate Type	Variable	Variable
Video Quality	Medium	Medium
Frame Rate	Full Frame	Full Frame
Max. Bitrate Mode	General	General
Max. Bitrate(Kbps)	1792	1792
Max. Bitrate Range Reco...	1344~2240(Kbps)	1344~2240(Kbps)
Pre-record	5s	
Post-record	5s	
Expired Time (day)	0	
Record Audio	<input checked="" type="checkbox"/>	
Enable 960Mode	<input checked="" type="checkbox"/>	

Copy Restore Apply Back

Figure 5.3 Encoding Parameters-Main Stream

## 2. Set encoding parameters for main stream

- 1) Select **Record** to enter the main stream settings interface.
- 2) Select the camera for configuration.
- 3) Configure the following parameters for the Main Stream (Normal) and the Main Stream (Event):
  - **Stream Type:** Set the stream type to be Video or Video & Audio.
  - **Resolution:** Set recording at resolution of WD1, 4CIF, 2CIF, CIF or QCIF.  
**Note:** The WD1 resolution is available for DS-7204HWI-SV, DS-7200HWI-SH, DS-7200HVI-SV and DS-7300HWI-SH models only.
  - **Bitrate Type:** Set the bitrate type to be Variable or Constant.
  - **Video Quality:** Set the video quality of recording, with 6 levels configurable.
  - **Frame Rate:** Set the frame rate of recording.
  - **Max. Bitrate Mode:** Set the mode to General or Customize (32-3072Kbps).
  - **Max Bitrate (Kbps):** Select or customize the maximum bit rate for recording.
  - **Max. Bitrate Range Recommended:** A recommended Max. bitrate range is provided for reference.
- 4) Configure the pre-record, post-record time, expired time, redundant record (this option is only available when the HDD mode is *Group*) and whether you want to record audio.
  - **Pre-record:** The time you set to record before the scheduled time or event. For example, when an alarm triggered the recording at 10:00, if you set the pre-record time as 5 seconds, the camera records it at 9:59:55.
  - **Post-record:** The time you set to record after the event or the scheduled time. For example, when an alarm triggered the recording ends at 11:00, if you set the post-record time as 5 seconds, it records till 11:00:05.
  - **Expired Time (day):** The expired time is the longest time for a record file to be kept in the

HDD, if the deadline is reached, the file will be deleted. You can set the expired time to 0, and then the file will not be deleted. The actual keeping time for the file should be determined by the capacity of the HDD.

- **Redundant Record:** Enabling redundant record means you save the record files in the redundant HDD. See *Chapter 5.8 Configuring Redundant Record*.

**Note:** The Redundant Record option is only available when the HDD mode is *Group*. The redundant record is to decide whether you want the camera to save the record files in the redundant HDD. You must configure the redundant HDD in HDD settings. For detailed information, see *Chapter 10.4.2 Setting HDD Property*.

- **Record Audio:** Check the checkbox to record the sound, or uncheck to record the image without sound.
- **Enable 960Mode:** Enable the encoding at WD1 (PAL: 960×576, NTSC: 960×480) resolution. You can also uncheck the checkbox to disable it.

**Note:** This feature is available for DS-7204HWI-SV, DS-7200HWI-SH, DS-7200HVI-SV and DS-7300HWI-SH models only.

- 5) If you want to copy the current main stream settings to other camera (s), click **Copy** to enter the Copy Camera interface. Select the camera (s) and click **OK** to finish the copy settings.




Figure 5.4 Copy Camera Settings

- 6) On the Record settings interface, click **Apply** to save the settings.

**Note:** You can click the **Restore** button to restore the current main stream settings to the default parameters.

### 3. Set encoding parameters for sub-stream

- 1) Click the **Substream** tab to enter the Substream settings interface.




Figure 5.5 Encoding Parameters-Sub-stream

- 2) Configure the parameters for the sub-stream. Refer to the step of main stream settings.
- 3) Click **Apply** to save the settings.

**Note:** You can click the **Restore** button to restore the current sub-stream settings to the default parameters.

- 4) If you want to copy the current sub-stream settings to other camera (s), click **Copy** to enter the Copy Camera interface. Select the camera (s) and click **OK** to finish the copy settings.

## 5.2 Configuring Record Schedule

### Purpose:

Set the record schedule, and then the camera automatically starts/stops recording according to the configured schedule.

### Steps:

1. Enter the Record Schedule interface.  
Menu>Record>Schedule
2. Configure Record Schedule
  - 1) Click **Schedule** to enter the record schedule settings interface.




Figure 5.6 Record Schedule

- 2) Choose the camera you want to configure.
  - 3) Check the check box after the **Enable Schedule** item.
- There are two ways to configure the record schedule.

### Task 1: Edit the Schedule

#### Steps:

- 1) Click **Edit**.
- 2) In the message box, you can choose the day which you want to set schedule.
- 3) To schedule an all-day recording, check ☒ checkbox to enable all-day recording.
- 4) Set the Type in the dropdown list. Different recording types are available for different models.  
DS-7200-SH/SV: Normal and Motion.  
DS-7300HFI-SH and DS-7300HWI-SH: Normal, Motion, Alarm, Motion/Alarm and Motion & Alarm.

**Note:** To enable Motion triggered recording, you must configure the motion detection settings as well. For detailed information, refer to *Chapter 8.1* and *Chapter 8.2*.

Schedule		Mon	
All Day	<input checked="" type="checkbox"/>	Type	Normal
Start/End Time	03:55-21:02	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal

Figure 5.7 Edit Schedule

5) To arrange other schedule, leave the **All Day** checkbox blank and set the Start/End time and Type.

**Note:** Up to 8 periods can be configured for each day. And the time periods can't be overlapped each other.

Repeat the above steps2)-5) to schedule recording for other days in the week. If the schedule can also be set to other days, click **Copy**.

Figure 5.8 Copy Schedule to Other Days

**Note:** The **Holiday** option is available in the Schedule dropdown list when you have enabled holiday schedule in **Holiday Settings**. Refer to *Chapter 5.5 Configuring Holiday Record*.

Holiday Name	Holiday1
Enable	<input checked="" type="checkbox"/>
Mode	By Date
Start Date	2012-02-07
End Date	2012-02-08

Figure 5.9 Holiday Settings

6) Click **OK** to save setting and back to upper level menu.



**Task 2: Draw the Schedule****Steps:**

- 1) Click the icon on the right to select a record type. Different recording types are available for different models.

DS-7200-SH/SV: Normal, Motion and None.

DS-7300HFI-SH and DS-7300HWI-SH: Normal, Motion, Alarm, M/A, M&A and None.

**Note:** To enable Motion triggered recording, you must configure the motion detection settings. For detailed information, refer to *Chapter 8.1* and *Chapter 8.2*.

- 2) Use the mouse to drag and draw time periods.

**Note:** Up to 8 periods can be configured for each day.




Figure 5. 10 Draw the Schedule

- 3) You can repeat the above steps to set schedule for other channels. If the settings can also be used to other channels, click **Copy** to enter the Copy Camera interface and then choose the channel to which you want to copy.



Figure 5.11 Copy Schedule to Other Channels

- 4) Click **Apply** in the Record Schedule interface to save the settings.

## 5.3 Configuring Motion Detection Record

### *Purpose:*

Follow the steps to set the motion detection parameters. In the live view mode, once a motion detection event takes place, the device can analyze it and perform some response actions to handle it. Enabling motion detection function can trigger certain channels to start recording, or trigger full screen monitoring, audio warning, notify the surveillance center and so on. In this chapter, you can follow the steps to schedule a record which triggered by the detected motion.

### *Steps:*

1. Enter the Motion Detection interface.

Menu>Camera>Motion




Figure 5.12 Motion Detection

2. Configure Motion Detection:

- 1) Choose camera you want to configure.
- 2) Check the checkbox after **Enable Motion Detection**.
- 3) Drag and draw the area for motion detection by mouse. If you want to set the motion detection for all the area shot by the camera, click **Full Screen**. To clear the motion detection area, click **Clear**.




Figure 5.13 Motion Detection- Mask

- 4) Click **Handling**, and the message box for channel information will pop up.




Figure 5.14 Motion Detection Handling

- 5) Select the channels which you want the motion detection event to trigger recording.
- 6) Click **Apply** to save the settings.
- 7) Click OK to back to the upper level menu.
- 8) Exit the Motion Detection menu.

3. Enter Schedule settings interface.

Menu> Record> Schedule>Record Schedule




Figure 5.15 Record Schedule

- 1) Check the checkbox after the **Enable Schedule** item.
- 2) Click **Edit**.




Figure 5.16 Edit Schedule- Motion Detection

- 3) In the message box, you can choose the day to which you want to set schedule.
- 4) Set the **Type** as **Motion**.

- 5) To schedule an all-day recording, check the checkbox after the **All Day** item.




Figure 5.17 Edit Schedule- All Day

- 6) To arrange other schedule, leave the **All Day** checkbox blank and set the Start/End time.

**Note:** Up to 8 periods can be configured for each day. And the time periods can't be overlapped each other.

Repeat the above steps 3)-6) to schedule motion detection triggered recording for all the week. If the schedule can also be set to other days, click **Copy**.




Figure 5.18 Copy Schedule to Other Days

- 7) Click **OK** to back to upper level menu.

If you can to copy the same schedule settings to other camera (s), click **Copy** to enter the Copy Camera interface, and then select the camera (s) you want to copy.



Figure 5.19 Copy Schedule to Other Channels

## 5.4 Configuring Alarm Triggered Record

**Note:** This section is available for DS-7300HWI/HFI-SH models only.

### **Purpose:**

Follow the procedure to configure alarm triggered recording or capture.

**Steps:**

1. Enter the Alarm setting interface.

Menu> Configuration> Alarm

The screenshot shows the 'Alarm Status' interface with three tabs: 'Alarm Status', 'Alarm Input', and 'Alarm Output'. The 'Alarm Status' tab is active, displaying two lists:

No.	Alarm Name	IP Camera Address	Alarm Type
A<-1		Local	N.O
A<-2		Local	N.O
A<-3		Local	N.O
A<-4		Local	N.O
A<-5		Local	N.O
A<-6		Local	N.O
A<-7		Local	N.O
A<-8		Local	N.O

No.	Alarm Name	IP Camera Address	Dwell Time
A->1		Local	5s
A->2		Local	5s
A->3		Local	5s
A->4		Local	5s

Figure 5.20 Alarm Settings

2. Click **Alarm Input** tab.

The screenshot shows the 'Alarm Input' configuration interface. It has three tabs: 'Alarm Status', 'Alarm Input', and 'Alarm Output'. The 'Alarm Input' tab is active, showing the following configuration fields:

Alarm Input No.	A<-1
Alarm Name	alarm01
Type	N.O
Setting	<input checked="" type="checkbox"/>
Handling	

Figure 5.21 Alarm Settings- Alarm Input

- 1) Select Alarm Input No. and configure alarm parameters.
- 2) Choose N.O (normally open) or N.C (normally closed) for alarm type.
- 3) Check ☒ checkbox to enable the alarm input.
- 4) Click to set the handling method.

The screenshot shows the 'Alarm Handling' configuration interface. It has four tabs: 'Trigger Channel', 'Arming Schedule', 'Handling', and 'PTZ Linking'. The 'Trigger Channel' tab is active, showing the following configuration:

Trigger Channel	Arming Schedule	Handling	PTZ Linking
<input type="checkbox"/> Analog	<input checked="" type="checkbox"/> A1 <input type="checkbox"/> A2 <input type="checkbox"/> A3 <input type="checkbox"/> A4 <input type="checkbox"/> A5 <input type="checkbox"/> A6		
	<input checked="" type="checkbox"/> A7 <input type="checkbox"/> A8 <input type="checkbox"/> A9 <input type="checkbox"/> A10 <input type="checkbox"/> A11 <input type="checkbox"/> A12		
	<input type="checkbox"/> A13 <input type="checkbox"/> A14 <input type="checkbox"/> A15 <input type="checkbox"/> A16		

Figure 5.22 Alarm Handling

- 5) Choose the alarm triggered recording/capture channel.
- 6) Check the checkbox ☒ to select channel.
- 7) Click **Apply** to save settings.
- 8) Click **OK** to back to the upper level menu.

9) Click **Apply** in the Alarm Input interface to save the settings.

Repeat the above steps to configure other alarm input parameters.

If the setting can also be applied to other alarm inputs, click **Copy** and choose the alarm input number.




Figure 5.23 Copy Alarm Input

3. Enter Record/Capture Schedule settings interface (Menu> Record> Schedule>Record Schedule). For detailed information about record schedule settings, refer to step 2 in *Chapter 5.2 Configuring Record/Capture Schedule*.

**Note:** You need to select the **Type** as Alarm in record schedule settings.




Figure 5.24 Record Schedule

## 5.5 Configuring Manual Record

### Purpose:

Follow the steps to set parameters for the manual record. When using manual record, you need to manually cancel the record. The manual recording is prior to the scheduled recording.

### Steps:

1. Enter the Manual settings interface.

Menu> Manual




Figure 5.25 Manual Record

2. Enable recording for camera (s).

Click the status button beside each camera number to change **OFF** to **ON**, or you can enable recording for all cameras by clicking the status bar before **Analog** to change it to **ON**.

3. Set recording mode to manual.

By default, the camera is enabled with recording by schedule (**ON**). Click the **ON** status bar to change it to **OFF** and click again to enable the recording to manual (**ON**).

**ON**: recording by schedule.

**ON**: recording by manual operation.

**Note:** After rebooting, all the manual records enabled are canceled.

4. Start all-day normal recording or all-day motion detection recording of all channels.

1) Click for **Normal** or **Motion Detection**.




Figure 5.26 Start Normal or Motion Detection Recording

2) Click **Yes** to enable all-day normal recording or all-day motion detection recording of all channels.


## 5.6 Configuring Holiday Record

### Purpose:

You may want to have different plan for recording on holiday. Follow the steps to configure the record schedule on holiday.

### Steps:


1. Enter the Record setting interface.  
Menu>Record
2. Choose **Holiday** on the left bar.



No.	Holiday Name	Status	Start Date	End Date	Edit
1	Holiday1	Enabled	1.Jan	1.Jan	
2	Holiday2	Disabled	1.Jan	1.Jan	
3	Holiday3	Disabled	1.Jan	1.Jan	
4	Holiday4	Disabled	1.Jan	1.Jan	
5	Holiday5	Disabled	1.Jan	1.Jan	
6	Holiday6	Disabled	1.Jan	1.Jan	
7	Holiday7	Disabled	1.Jan	1.Jan	
8	Holiday8	Disabled	1.Jan	1.Jan	
9	Holiday9	Disabled	1.Jan	1.Jan	
10	Holiday10	Disabled	1.Jan	1.Jan	
11	Holiday11	Disabled	1.Jan	1.Jan	
12	Holiday12	Disabled	1.Jan	1.Jan	

Figure 5.27 Holiday Settings

3. Enable Edit Holiday schedule.
  - 1) Click to enter the Edit interface.



Edit	
Holiday Name	Holiday1
Enable	<input checked="" type="checkbox"/>
Mode	By Date
Start Date	02-07-2012
End Date	02-08-2012
<div> <input type="button" value="Apply"/> <input type="button" value="OK"/> <input type="button" value="Cancel"/> </div>	

Figure 5.28 Edit Holiday Settings

- 2) Check the checkbox after **Enable**.
- 3) Select Mode from the dropdown list.  
There are three different modes for the date format to configure holiday schedule.
- 4) Set the start and end date.



- 5) Click **Apply** to save settings.
- 6) Click **OK** to exit the Edit interface.
4. Enter Record Schedule settings interface.  
Menu> Record> Schedule
  - 1) Select **Record**.
  - 2) Check the checkbox after **Enable Schedule**.
  - 3) Click **Edit**.
  - 4) Select **Holiday** from the **Schedule** dropdown list.

Edit			
Schedule		Holiday	
All Day	<input checked="" type="checkbox"/>	Type	Motion   Alarm
Start/End Time	00:02-24:00	Type	Motion   Alarm
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal
Start/End Time	00:00-00:00	Type	Normal

Copy Apply OK Cancel

Figure 5.29 Edit Schedule- Holiday

- 5) Select **Motion** or **Normal** from the **Type** dropdown list.
- 6) If you need all day recording, check the **All Day** checkbox. Otherwise leave it blank.
- 7) Set start/end time for holiday schedule.

**Note:** Up to 8 periods can be configured for each day. And the time periods can't be overlapped each other.

In the time table of the channel, both holiday schedule and normal day schedule are displayed.

Repeat the above steps4)-7) to set Holiday schedule for other channel. If the holiday schedule can also be used to other channels, click **Copy** and choose the channel you want to apply the settings.

## 5.7 Configuring Redundant Record

### Purpose:

Enabling redundant recording, which means saving the record files not only in the R/W (read/write) HDD but also in the redundant HDD, will effectively enhance the data safety and reliability.

**Note:** You must set the Storage mode in the HDD advanced settings to Group before you set the HDD property to Redundant. For detailed information, please refer to *Chapter 10.4 Managing HDD Group*. There should be at least another HDD (NetHDD) which is in R/W mode.

### Steps:

1. Enter HDD Information interface.

Menu> HDD





Figure 5.30 HDD General

2. Select the **HDD** and click  to enter the Local HDD Settings interface.

- 1) Set the HDD property to Redundant.




Figure 5.31 HDD General-Editing

- 2) Click **Apply** to save the settings.
- 3) Click **OK** to back to the upper level menu.
3. Enter the Record setting interface.  
Menu> Record> Encoding
  - 1) Select **Record**.




Figure 5.32 Encoding Record

- 2) Select Camera you want to configure.
- 3) Check the checkbox of the **Redundant Record**.
- 4) Click **Apply** to save settings and back to the upper level menu.

Repeat the above steps2)-4) for configuring other channels.

## 5.8 Configuring HDD Group for Record

### *Purpose:*

You can group the HDDs and save the record files in certain HDD group.

### *Steps:*

1. Enter HDD setting interface.  
Menu>HDD





Figure 5.33 HDD-General

2. Select **Advanced** on the left bar.  
Check whether the storage mode of the HDD is Group. If not, set it to Group. For detailed information, please refer to *Chapter 10.4 Managing HDD Group*.
3. Select **General** in the left bar.

Click  to enter editing interface.

**4. Configuring HDD group.**

- 1) Choose a group number for the HDD group.
- 2) Click **Apply** and then in the pop-up message box, click **Yes** to save your settings.
- 3) Click **OK** to back to the upper level menu.

Repeat the above steps 3-4 to configure more HDD groups.

**5. Choose the Channels which you want to save the record files in the HDD group.**

- 1) Select **Advanced** on the left bar.




Figure 5.34 HDD-Advanced

- 2) Choose Group number in the dropdown list of **Record on HDD Group**.
- 3) Check the channels you want to save in this group.
- 4) Click **Apply** to save settings.

**Note:** After having configured the HDD groups, you can configure the Recording settings following the procedure provided in *Chapter 5.2-5.6*.

## 5.9 Files Protection

### Purpose:

You can lock the recorded files or set the HDD property to Read-only to protect the record files from being overwritten.

### Protect file by locking the record files:

#### Steps:

1. Enter Playback setting interface.

Menu> Playback





Figure 5.35 Playback

2. Select the channels by checking the checkbox to .
3. Configure the record type, file type and start/end time.
4. Click **Search** to show the results.






Figure 5.36 Playback- Search Result

5. Protect the record files.

- 1) Find the record files you want to protect, and then click the  icon which will turn to , indicating that the file is locked.

**Note:** The record files of which the recording is still not completed can't be locked.



- 2) Click  to change it to  to unlock the file and the file is not protected.



Figure 5.37 Unlocking Attention

#### Protect file by setting HDD property to Read-only

**Note:** To edit HDD property, you need to set the storage mode of the HDD to Group. See *Chapter 10.4 Managing HDD Group*.

#### Steps:

1. Enter HDD setting interface.

Menu> HDD




Figure 5.38 HDD General

2. Click  to edit the HDD you want to protect.




Figure 5.39 HDD General- Editing

3. Set the HDD to Read-only.
4. Click **OK** to save settings and back to the upper level menu.

**Note:** You can't save any files in a Read-only HDD. If you want to save files in the HDD, change the property to R/W.

**Note:** If there is only one HDD and is set to Read-only, the device can't record any files. Only live view mode is available.

If you set the HDD to Read-only when the device is saving files in it, then the file will be saved in next R/W HDD. If there is only one HDD, the recording will be stopped.

# **C H A P T E R 6**

## **Playback**



## 6.1 Playing Back Record Files


### 6.1.1 Playing Back by Channel

**Purpose:**

Play back the recorded video files of a specific channel in the live view mode. Channel switch is supported.

**Instant playback by channel:**

**Steps:**

Choose a channel in live view mode using the mouse and click the  button in the quick setting toolbar.

**Note:** Only record files recorded during the last five minutes on this channel will be played back.



Figure 6.1 Instant Playback Interface

---

**All-day Playback by channel**

1. Enter the All-day Playback interface.

Mouse: right click a channel in live view mode and select All-day Playback from the menu, as shown in Figure 6.2.




Figure 6.2 Right-click Menu under Live View

Press **PLAY** button on the IR remote control to play back record files of the channel under single-screen live view.

Under multi-screen live view, record files of the top left channel (not masked) will be played back.

**Note:** Pressing numerical buttons will switch playback to the corresponding channels during playback process.

## 2. Playback management.

The toolbar in the bottom part of Playback interface can be used to control playing progress, as shown in Figure 6.3.



Figure 6.3 All-day Playback Interface

The channel and time selection menu displays by moving the mouse to the right of the playback interface.

Click the channel(s) if you want to switch playback to another channel or execute simultaneous playback of multiple channels, as shown in Figure 6.4.



Figure 6.4 All-day Playback Interface with Channel List

Dates marked in different colors:

- 11 : No record files in this day.
- 19 : There is record file(s) in this day (not current day).
- 20 : There is only event recording file(s) in this day (not current day).
- 10 : Mouse cursor is located.



Figure 6.5 Toolbar of All-day Playback

Table 6.1 Detailed Explanation of All-day-playback Toolbar

Button	Operation	Button	Operation	Button	Operation	Button	Operation
	Audio on /Mute		Start/Stop clipping		30s forward		30s reverse
	Add default tag		Add customized tag		Tag management		Speed down
	Pause reverse play/ Reverse play/ Single-frame reverse play		Pause play/ Play/ Single-frame play		Stop		Speed up
	Previous day		Next day		Hide		Exit
	Process bar		Video type bar				

#### Notes:

1. Playback progress bar: use the mouse to click any point of the progress bar or drag the progress bar to locate special frames.

- About video type bar: ■ represents normal recording (manual or schedule); ■ represents event recording; ■ represents smart search recording.

## 6.1.2 Playing Back by Time

### *Purpose:*

Play back video files recorded in specified time duration. Multi-channel simultaneous playback and channel switch are supported.

### *Steps:*

- Enter playback interface.  
Menu>Playback
- Check the checkbox before the channel to select channel(s) and click the **Detail** button to view the record information of the channel(s). You can click **Previous** or **Next** to select the day for viewing the record information.



Figure 6.6 Record Information

- Click **Back** to return to the playback interface.
- Set search conditions and click the **Playback** button to enter Playback interface.




Figure 6.7 Video Search by Time

In the Playback interface:

The toolbar in the bottom part of Playback interface can be used to control playing process, as shown in Figure 6.7.



Figure 6.8 Interface of Playback by Time




Figure 6.9 Toolbar of Playback by Time

Table 6.2 Detailed Explanation of Playback-by-time Toolbar

Button	Operation	Button	Operation	Button	Operation	Button	Operation
	Audio on/Mute		Start/Stop clipping		30s forward		30s reverse
	Add default tag		Add customized tag		Tag management		Speed down
	Pause reverse play/Reverse play/Single-frame reverse play		Pause play/Play/Single-frame play		Stop		Speed up
	Video search		Exit		Hide		Progress bar
	Video type bar						

**Notes:**

1. Playback progress bar: use the mouse to click any point of the progress bar or drag the progress bar to locate special frames.
2. About video type bar: represents normal recording (manual or schedule); represents event recording; represents smart search recording.

## 6.1.3 Playing Back by Normal Video Search

**Purpose:**

Play back video files searched out by restricting recording type and recording time. The video files in the result list are played back sequentially and channel switch is supported. Recording types contain Normal, Motion and Manual.

**Steps:**

1. Enter Record File Search interface.  
Menu>Playback  
Set search condition and click **Search** button to enter the Search Result interface.






Figure 6.10 Normal Video Search

## 2. Choose a record file you want to play back.

If there is only one channel in the search result, clicking  button takes you to Full-screen Playback interface of this channel.

If more than one channel is optional, clicking  button takes you to step 3 and step 4.




Figure 6.11 Result of Normal Video Search

## 3. Choose channels for simultaneous playback.

**Note:** Optional channels for simultaneous playback are the same as the channels chosen to search record files in step 1. And the channel with the recorded file selected in step 2 is the main channel during multi-channel playback and it is displayed at the upper left corner.




Figure 6.12 Select Channels for Synchronous Playback

## 4. Synchronous Playback interface.

The toolbar in the bottom part of Playback interface can be used to control playing process.





Figure 6.13 4-ch Synchronous Playback Interface

The hidden list of recorded files displays by moving the mouse to the right of the playback interface.



Figure 6.14 4-ch Synchronous Playback Interface with Video List




Figure 6.15 Toolbar of Normal Playback

Table 6.3 Detailed Explanation of Normal Playback Toolbar

Button	Operation	Button	Operation	Button	Operation	Button	Operation
	Audio on/Mute		Start/Stop clipping		30s forward		30s reverse
	Add default tag		Add customized tag		Tag management		Speed down
	Pause reverse play/Reverse play/Single-frame reverse		Pause play/Play/Single-frame play		Stop		Speed up



	play						
◀	Previous file	▶	Next file	📺	Video search	✕	Exit
🔍	Hide toolbar	📊	Progress bar	▬	Video type bar		

**Note:**

1. Playback progress bar: use the mouse to click any point of the progress bar or drag the progress bar to locate special frames.
2. About video type bar: ■ represents normal recording (manual or schedule); ■ represents event recording; ■ represents smart search recording.

## 6.1.4 Playing Back by Event Search

**Purpose:**

Play back record files on one or several channels searched out by restricting event type (motion detection or alarm input). Channel switch is supported.

**Note:** Playback by alarm input search is supported by DS-7300HWI/HFI-SH only.

**Steps:**

1. Enter the playback interface.  
Menu>Playback
2. Select **Event** tab to enter the Event Playback interface.
3. Select **Motion** or **Alarm Input** as the event type.
4. Set the start time and end time for the selected event.




Figure 6.16 Video Search by Alarm Input




Figure 6.17 Video Search by Motion Detection

5. Select the camera (s) for searching of motion detected triggered record files or select the alarm input (s) for the alarm triggered record files.
6. Click **Search** button to enter the Search Result interface.




Figure 6.18 Search Result of Alarm Input




Figure 6.19 Search Result of Motion Detection

The Pre-play and post-play can be configured. The **Pre-play** refers to the time configured before the defined start time of event search, and the **Post-play** refers to the time configured after the defined end time of event search. For example, when the start time and end time of event search are set to 12:00:00 - 13:00:00, and the pre-play and post-play time is set to 30s and 20s respectively, then the actual playback of event video file is 11:59:30 ~ 13:00:20.

7. You can select an item from the list and click **Details** to view detailed information of the record file, e.g. start time, end time, file size, etc.




Figure 6.20 Event Details

Or you can directly click the button of each file item to enter its playback interface. The toolbar in the bottom part of Playback interface can be used to control playing process.



Figure 6.21 Interface of Playback by Event (1)

The hidden list of events will be displayed by moving the mouse to the right of the playback interface.



Figure 6.22 Interface of Playback by Event (2)








Figure 6.23 Toolbar of Playback by Event

Table 6.4 Detailed Explanation of Playback-by-event Toolbar

Button	Operation	Button	Operation	Button	Operation	Button	Operation
	Audio on/Mute		Start/Stop clipping		30s forward		30s reverse

	Add default tag		Add customized tag		Tag management		Speed down
	Pause reverse play/Reverse play/Single-frame reverse play		Pause play/Play/Single-frame play		Stop		Speed up
	Previous event		Next event		Event search		Exit
	Hide		Progress bar		Video type bar		

**Notes:**

1. Playback progress bar: use the mouse to click any point of the progress bar or drag the progress bar to locate special frames.
2. About video type bar:  represents normal recording (manual or schedule);  represents event recording;  represents smart search recording.

## 6.1.5 Playing Back by Tag

**Purpose:**


Video tag allows you to record related information like people and location of a certain time point during playback. You are also allowed to use video tag(s) to search for record files and position time point.


**Before playing back by tag:**

1. Enter Playback interface.




Figure 6.24 Interface of Playback by Time

Click  button to add default tag.

Click  button to add customized tag and input tag name.

**Note:** Max. 64 tags can be added to a single video file.

## 2. Tag management.

Click  button to check, edit and delete tag(s).




Figure 6.25 Tag Management Interface

### Steps:

#### 1. Enter Playback interface.

Menu>Playback

Click **Tag** tab to enter Playback by Tag interface.

Choose channels, tag type and time, and click **Search** to enter Search Result interface.

**Note:** Two tag types are selectable: *All* and *Tag Keyword*. Input keyword if you choose *Tag Keyword*.




Figure 6.26 Video Search by Tag

#### 2. Set playback conditions and tag management.

Choose the tag name of the recorded file you want to play back; it can be edited or deleted.

Pre-play and post-play time can be set according to actual needs.

**Note:** Pre-play time and post-play time is added to the time point of the tag.



Figure 6.27 Result of Video Search by Tag

### 3. Playback by tag.


Choose a tag and click  button to play back the related record file.



Figure 6.28 Interface of Playback by Tag

The hidden list of tags will be displayed by moving the mouse to the right of the playback interface.





Figure 6.29 Interface of Playback by Tag with Video List




Figure 6.30 Toolbar of Playback by Tag

Table 6.5 Detailed Explanation of Playback-by-tag Toolbar

Button	Operation	Button	Operation	Button	Operation	Button	Operation
	Audio on/Mute		Start/Stop clipping		30s forward		30s reverse
	Add default tag		Add customized tag		Tag management		Slow down
	Pause reverse play/Reverse play/Single-frame reverse play		Pause play/Play/Single-frame play		Stop		Speed up
	Previous tag		Next tag		Tag search		Exit
	Hide		Progress bar		Video type bar		

**Notes:**

1. Playback progress bar: use the mouse to click any point of the progress bar or drag the progress bar to locate special frames.
2. About video type bar: represents normal recording (manual or schedule); represents event recording; represents smart search recording.



## 6.1.6 Playing Back by System Log

### Purpose:

Play back record file(s) associated with channels after searching system logs.

### Steps:

1. Enter Log Search interface.

Menu>Maintenance>Log Search



Figure 6.31 System Log Search Interface

2. Set search time and type and click **Search** button.



Figure 6.32 Result of System Log Search

3. Choose a log with record file and click  button to enter Playback interface.

**Note:** If there is no record file at the time point of the log, the message box “No result found” will pop up.

The toolbar in the bottom part of Playback interface can be used to control playing process.



Figure 6.33 Interface of Playback by Log

---

## 6.2 Auxiliary Functions of Playback






### 6.2.1 Playing Back Frame by Frame

**Purpose:**

Play video files frame by frame, in order to check image details of the video when abnormal events happen.



**Steps:**

- **Using a Mouse:**

Go to Playback interface. If you choose playback of the record file: click button  and  until the speed changes to *Single* frame and one click on the playback screen represents playback of one frame. If you choose adverse playback of the record file: click button  and  until the speed changes to *Single* frame and one click on the playback screen represents adverse playback of one frame. It is also feasible to use button  in toolbar.

- **Using the Front Panel :**

For DS-7300HWI/HFI-SH DVR, you can use the front panel buttons to perform the playback.

Rotate and hold the outer ring on Jog Shuttle counterclockwise or click the  button to set the speed to *Single* frame. One click on button , one click on the playback screen or **Enter** button on the front panel represents playback or reverse playback of one frame.

### 6.2.2 Smart Search

**Purpose:**

In order to locate motion detection event easily and accurately in the playback progress bar, you are allowed to analyze a certain area (scene) dynamically, and to get all of the related motion detection events that occurred in this area.

**Steps:**

1. Go to normal playback or all-day playback interface.

**Note:** The smart search function is available for single-channel playback only.



Figure 6.34 Playback Interface

2. Right-click mouse and select **Smart Search** to go to analysis area selection interface.






Figure 6.35 Right-click Menu in All-day Playback and Normal Playback Interface

3. You can click button  to set the full screen as target searching area. After drawing area(s), click button  to execute smart search in this area.

**Note:** Multi-area and full-screen searching modes are supported.




Figure 6.36 Draw Area of Smart Search

Different video type bars are marked in different colors:

- : Normal record file;
- : Event record file;
- : Smart search record file.

The hidden list of record files display when moving the mouse to the right of the playback interface.



Figure 6.37 Smart Search Result with Video List




Figure 6.38 Toolbar of Smart Search Playback

Table 6.6 Detailed Explanation of Smart-search-playback Toolbar

Button	Operation	Button	Operation	Button	Operation	Button	Operation
	Audio on/Mute		Start/Stop clipping		30s forward		30s reverse
	Add default tag		Add customized tag		Tag management		Slow down
	Pause reverse play/Reverse play/Single-frame reverse play		Pause play/Play/Single-frame play		Stop		Speed up
	Previous smart search result		Next smart search result		Video search		Exit
	Hide		Progress bar		Video type bar		Smart search bar

**Notes:**

1. Playback progress bar: use the mouse to click any point of the progress bar or drag the progress bar to locate special frames.
2. About video type bar: ■ represents normal recording (manual or schedule); ■ represents event recording; ■ represents smart search recording.

## 6.2.3 Digital Zoom

### Steps:

1. Right click the mouse on a channel under playback and choose Digital Zoom to enter Digital Zoom interface.
2. Use the mouse to draw a red rectangle and the image within it will be enlarged up to 16 times.



Figure 6.39 Draw Area for Digital Zoom









Figure 6.40 Right-click Menu in Playback Mode

### Right-click menu:

**Note:** This menu differs slightly from one playback interface to another.

Table 6.7 Detailed Explanation of Right-click Menu under Playback

Button	Function
	Return to Playback interface
	Enter Digital Zoom interface
	Smart Search against a specified area
	Show & hide control interface
	Exit the video playback interface

# **CHAPTER 7**

## **Backup**

## 7.1 Backing up Record Files

### *Before you start:*

Please insert the backup device(s) into the device.

### 7.1.1 Quick Export

#### *Purpose:*

Export record files to backup device(s) quickly.

#### *Steps:*

1. Enter Video Export interface.

Menu>Export>Normal



Figure 7.1 Quick Export Interface

2. Choose the channel(s) you want to back up and click **Quick Export** button.

#### *Notes:*

1. The time duration of record files on a specified channel cannot exceed 24 hours. Otherwise, the message box “Max. 24 hours are allowed for quick export.” will pop up.
2. The number of channels for synchronous export cannot exceed 4. Otherwise, the message box “Max. 4 channels are allowed for synchronous quick export.” will pop up.





Figure 7.2 Quick Export using USB1-1

- In the Export interface, choose backup device and click **Export** button to start exporting.

**Note:** Here we use USB Flash Drive and please refer to the next section Normal Backup for more backup devices supported by the device.

- Stay in the Exporting interface until all record files are exported to the USB flash drive.




Figure 7.3 Export Finished

- Check backup result.

Choose the record file in Export interface and click button  to check it.

**Note:** The Player player.exe will be exported automatically during record file export.



Figure 7.4 Checkup of Quick Export Result Using USB1-1

## 7.1.2 Backing up by Normal Video Search

### *Purpose:*

The record files can be backup to various devices, such as USB devices (USB flash drives, USB HDDs, USB writer) and SATA writer.

### **Backup using USB flash drives, USB HDDs, USB writer and SATA writer**

### *Steps:*


1. Enter Export interface.

Menu>Export>Normal



Figure 7.5 Normal Video Search for Backup

2. Set search conditions and click **Search** button to enter the search result interface.
3. Select record files you want to back up.

Click button  to play the record file if you want to check it.

Check the checkbox before the record files you want to back up.

**Note:** The size of the currently selected files is displayed in the lower-left corner of the window.




Figure 7.6 Result of Normal Video Search for Backup

#### 4. Export the record files.

Click **Export** button and start backup.

**Note:** If the inserted device is not recognized:

- Click the **Refresh** button.
- Reconnect device.
- Check for compatibility from vendor.

You can also format USB flash drives or USB HDDs via the device. USB writer and SATA writer cannot be formatted.



Figure 7.7 Export by Normal Video Search using USB Flash Drive



Figure 7.8 Export by Normal Video Search using USB Writer

Stay in the Exporting interface until all record files are exported with pop-up message box “Export finished”.





Figure 7.9 Export Finished

##### 5. Check backup result.

Choose the record file in Export interface and click button  to check it.

**Note:** The Player player.exe will be exported automatically during record file export.



Figure 7.10 Checkup of Export Result using USB Flash Drive



Figure 7. 11 Checkup of Export Result using USB Writer

### 7.1.3 Backing up by Event Search

#### *Purpose:*

Back up event-related record files using USB devices (USB flash drives, USB HDDs, USB writer), or SATA writer. Quick Backup and Normal Backup are supported.

**Note:** Backup by alarm input search is supported by DS-7300HWI/HFI-SH only.

#### *Steps:*

1. Enter Export interface.  
Menu>Export>Event
2. Select **Motion** or **Alarm Input** as the event type.  
**Note:** The following steps have introduced the backup by motion detection triggered record files.  
Perform the same operation for the backup by alarm triggered record files.
3. Set the start time and end time of the record files.
4. Select the camera (s) for searching.




Figure 7.12 Event Search for Backup

5. Click **Search** button to enter the Search Result interface.




Figure 7.13 Result of Event Search

6. Select record files to export. You can use the following two ways to enter the Export interface.
  - Select motion detection event (s) from the list and click **Quick Export** button to enter the Export interface, as shown in Figure 7.14.
  - (1) Click the **Details** button to enter the interface with detailed information of the record file, e.g., start time, end time, file size, etc.  
**Note:** The size of the currently selected files is displayed in the lower-left corner of the window.  
 (2) Select record file (s) from the list and click **Export** button to enter the Export interface, as shown in Figure 7.14.




Figure 7.14 Event Details Interface

7. Export the selected record files.  
 Click the **Export** button and start backing up.  
**Note:** If the inserted USB device is not recognized:
  - Click the Refresh button.
  - Reconnect device.
  - Check for compatibility from vendor.

You can also format USB flash drive or USB HDDs via the device.



Figure 7.15 Export by Event Using USB Flash Drive

Stay in the Exporting interface until all record files are exported with pop-up message "Export finished".




Figure 7.16 Export Finished

## 8. Check backup result.

Choose the record file in Export interface and click button  to check it.

**Note:** The Player player.exe will be exported automatically during record file export.






Figure 7.17 Checkup of Event Export Result Using USB Flash Drive

## 7.1.4 Backing up Video Clips

### *Purpose:*

You may also select video clips to export directly during Playback, using USB devices (USB flash drives, USB HDDs, USB writer), or SATA writer.

### *Steps:*

1. Enter Playback interface.  
Please refer to *Chapter 6*.
2. During playback, use buttons  and  in the playback toolbar to start or stop clipping record file(s).
3. Exit Playback interface after finishing clipping and you will then be prompted to save the clips.

**Note:** A maximum of 30 clips can be selected for each channel.



Figure 7.18 Interface of Playback by Time

4. Click **Yes** to save video clips and enter Export interface, or click **No** to quit and do not save video clips.




Figure 7.19 Attention to Video Clip Saving

5. Export the video clips.

Click **Export** button and start backing up.

**Note:** If the inserted USB device is not recognized:

- Click the **Refresh** button.
- Reconnect device.
- Check for compatibility from vendor.

You can also format USB flash drive or USB HDDs via the device.






Figure 7.20 Export Video Clips Using USB Flash Drive

Stay in the Exporting interface until all record files are exported with pop-up message “Export finished”.




Figure 7.21 Export Finished

#### 6. Check backup result.

**Note:** The Player player.exe will be exported automatically during record file export.




Figure 7.22 Checkup of Video Clips Export Result Using USB Flash Drive

## 7.2 Managing Backup Devices

### Management of USB flash drive, USB HDD and eSATA HDD.

**Note:** The eSATA HDD is supported by DS-7300HWI/HFI-SH models only.

1. Enter Search Result interface of record files.

Menu>Export>Normal

Set search condition and click **Search** button to enter Search Result interface.

**Note:** At least one channel shall be selected.



Figure 7.23 Normal Video Search

2. Select record files you want to back up.

Click **Export** button to enter Export interface.

**Note:** At least one record file shall be selected.





Figure 7.24 Result of Normal Video Search for Backup

### 3. Backup device management.

Click **New Folder** button if you want to create a new folder in the backup device.

Select a record file or folder in the backup device and click button  if you want to delete it.

Select a record file in the backup device and click button  to play it.

Click **Format** button to format the backup device.

**Note:** If the inserted USB device is not recognized:

- Click the **Refresh** button.
- Reconnect device.
- Check for compatibility from vendor.



Figure 7.25 USB Flash Drive Management

### Management of USB writers and DVD-R/W

#### 1. Enter Search Result interface of record files.

Menu>Export>Normal

Set search condition and click **Search** button to enter Search Result interface.

**Note:** At least one channel shall be selected.



Figure 7.26 Normal Video Search for Backup

2. Select record files you want to back up.

Click **Export** button to enter Export interface.

**Note:** At least one record file shall be selected.




Figure 7.27 Result of Normal Video Search for Backup

3. Backup device management.

Click **Erase** button if you want to erase the files from a re-writable CD/DVD.

**Note:** There must be a re-writable CD/DVD when you make this operation.

**Note:** If the inserted USB writer or SATA writer is not recognized:

- Click the **Refresh** button.
- Reconnect device.

- Check for compatibility from vendor.



Figure 7.28 USB Writer Management

---

# **C H A P T E R 8**

## **Alarm Settings**

## 8.1 Setting Motion Detection

*Steps:*

1. Enter Motion Detection interface and choose a camera you want to set motion detection.

Menu> Camera> Motion



Figure 8.1 Motion Detection Setup Interface

2. Set motion detection area and sensitivity.


- 1) Check the checkbox of **Enable Motion Detection** to enable motion detection, use the mouse to draw detection area(s) and drag the sensitivity bar to set sensitivity.
- 2) Click the  icon of **Handling** to set alarm response actions.



Figure 8.2 Set Detection Area and Sensitivity

3. Click **Trigger Channel** tab and select one or more channels which will start to record or become full-screen monitoring when motion alarm is triggered.



Figure 8.3 Set Trigger Camera of Motion Detection

4. Set up arming schedule of the channel.

- 1) Select **Arming Schedule** tab to set the channel's arming schedule.
- 2) Choose one day of a week and up to eight time periods can be set within each day.
- 3) Click **Apply** to save the arming settings of the selected day.
- 4) Repeat the above steps to set up arming schedule of other days of a week. You can also use **Copy** button to copy an arming schedule to other days.

**Note:** Time periods shall not be repeated or overlapped.




Figure 8.4 Set Arming Schedule of Motion Detection

5. Click **Handling** tab to set up alarm response actions of motion alarm (please refer to *Chapter 8.6*).



Figure 8.5 Set Alarm Response Actions of Motion Detection

**Note:** The Trigger Alarm Output option is available for DS-7300HWI/HFI-SH models only.

6. Click **OK** to complete the motion detection settings of the channel.
7. If you want to set up motion detection for another channel (s), repeat the above steps or copy the above settings to the channel (s).

**Note:** You are not allowed to copy the "Trigger Channel" action.





Figure 8.6 Copy Settings of Motion Detection

## 8.2 Setting Sensor Alarms

**Note:** This section is available for DS-7300HWI/HFI-SH models only.

**Purpose:**

You can set handling method of an external sensor alarm.

**Steps:**

1. Enter Alarm Settings interface and select an alarm input.

Menu> Configuration> Alarm





Figure 8.7 Alarm Status Interface

2. Select **Alarm Input** tab to enter Alarm Input Settings interface and set the handling method of the selected alarm input.

Check ☒ checkbox to enable the alarm input and click  to set up its alarm response actions.

Alarm Status	Alarm Input	Alarm Output
Alarm Input No.	A<- 1	
Alarm Name		
Type	N.C	
Setting	<input checked="" type="checkbox"/>	
Handling		

Figure 8.8 Alarm Input Settings Interface

3. Select **Trigger Channel** tab and select one or more channels which will start to record/capture or become full-screen monitoring when an external alarm is input. Click **Apply** to save the settings.
4. Select **Arming Schedule** tab to set the channel's arming schedule.  
Choose one day of a week and up to eight time periods can be set within each day. Set up arming schedule of other days of a week. You can also use **Copy** to copy an arming schedule to other days. Click **Apply** to save the settings.  
**Note:** Time periods shall not be repeated or overlapped.
5. Select **Handling** tab to set alarm response actions of the alarm input (please refer to *Chapter 8.6*).

Handling	
Trigger Channel	Arming Schedule
Week	Mon
1	00:00-24:00
2	00:00-00:00
3	00:00-02:00
4	00:00-00:00
5	00:00-00:00
6	00:00-00:00
7	00:00-00:00
8	00:00-00:00

Copy Apply OK Cancel

Figure 8.9 Set Arming Schedule of Alarm Input

6. If necessary, select **PTZ Linking** tab and set PTZ linkage of the alarm input.  
Set PTZ linking parameters and click **Apply** to save the settings. Click **OK** to complete the settings of the alarm input.  
**Note:** Please check whether the PTZ or speed dome supports PTZ linkage.  
One alarm input can trigger presets, patrol or pattern of more than one channel. But presets, patrols and patterns are exclusive.



Figure 8.10 Set PTZ Linking of Alarm Input

7. If you want to set handling method of another alarm input, repeat the above steps or just copy the above settings to it by clicking **Copy** in Alarm Input Settings interface.




Figure 8.11 Copy Settings of Alarm Input

## 8.3 Detecting Video Loss

### Purpose:

Detect video loss of a channel and take alarm response action(s).

### Steps:

1. Enter Video Loss interface of Camera Management.

Menu> Camera> Video Loss





Figure 8.12 Video Loss Setup Interface

2. Select a channel you want to detect.
3. Check the checkbox of **Enable Video Loss Alarm**.
4. Click the  icon of **Handling** to enter the Handling interface.
5. Set the arming schedule and alarm response actions. Please refer to **Step4** and **Step5** of *Chapter 8.1 Setting up Motion Detection Alarm*.




Figure 8.13 Set Arming Schedule of Video Loss

6. Click **Apply** to save the video loss alarm settings.

## 8.4 Detecting Video Tampering

### Purpose:

Trigger alarm when the lens is covered and take alarm response action(s).

### Steps:

1. Enter Video Tampering interface of Camera Management.

Menu> Camera> Tamper-proof




Figure 8.14 Tamper-proof Setup Interface

2. Select a channel you want to detect video tampering.

3. Check the checkbox of **Enable Tamper-proof**.

**Note:** By default, the tamper-proof detection is configured in full screen.

4. Move the sensitivity bar and choose a proper sensitivity level.

5. Click the  icon of **Handling** to enter the Handling interface.

6. Set the arming schedule and alarm response actions. Please refer to **Step4** and **Step5** of *Chapter 8.1 Setting up Motion Detection Alarm*.

7. If you want to set video loss handling method for another channel, repeat above steps or click **Copy** to copy the above settings to it.



Figure 8.15 Copy Settings of Video Tampering

## 8.5 Handling Exceptions

### *Purpose:*

Exception settings refer to the handling method of various exceptions, e.g.,

- **HDD Full:** The HDD is full.
- **HDD Error:** Writing HDD error, unformatted HDD, etc.
- **Network Disconnected:** Disconnected network cable.
- **IP Conflicted:** Duplicated IP address.
- **Illegal Login:** Incorrect user ID or password.
- **Input / Output Video Standard Mismatch:** I/O video standards do not match.
- **Record Exception:** No space for saving recorded file.

### *Steps:*

Enter **Exceptions** interface of System Configuration and handle various exceptions.

Menu> Configuration> Exceptions

Please refer to *Chapter 8.5* for detailed alarm response actions.




Figure 8.16 Exceptions Setup Interface

---

## 8.6 Setting Alarm Response Actions

### **Purpose:**

The alarm response actions will be activated when an exception occurs, including Full Screen Monitoring, Audible Warning, Notify Surveillance Center, and Send Email.

### **Full Screen Monitoring**

When an alarm event (motion detection/tamper-proof/video loss detection) is triggered, the local monitor (HDMI/VGA or BNC monitor) display in full screen the video image from the alarming channel configured for full screen monitoring.

If alarms are triggered simultaneously in several channels, their full-screen images will be switched at an interval of 10 seconds (default dwell time). A different dwell time can be set by going to Menu> Configuration>Live View>Full Screen Monitoring Dwell Time.

Auto-switch will terminate once the alarm stops and you will be taken back to the Live View interface.

**Note:** For motion detection alarm, you must select the channel(s) you want to make full screen monitoring (Menu>Camera>Motion>Handling>Trigger Channel).

### **Audible Warning**

Trigger an audible *beep* when an alarm is detected.

### **Notify Surveillance Center**

Sends an exception or alarm signal to remote alarm host when an event occurs. The alarm host refers to the PC installed with Remote Client.

**Note:** The alarm signal will be transmitted automatically at detection mode when remote alarm host is configured. Please refer to *Chapter 9.2.6* for details of alarm host configuration.

### **Send Email**

Send an email with alarm information to a user or users when an alarm event is detected.

Please refer to *Chapter 9.2.10* for details of Email configuration.

### **Trigger Alarm Output**

**Note:** This feature is available for DS-7300HWI/HFI-SH models only.

Trigger an alarm output when an alarm is triggered.

#### **Steps:**

1. Enter Alarm Output interface.

Menu> Configuration> Alarm> Alarm Output


Select an alarm output and set alarm name and dwell time.

**Note:** If “Manually Clear” is selected in the dropdown list of Dwell Time, you can clear it only by going to Menu> Manual> Alarm and clicking **Clear All**.

Alarm Status	Alarm Input	Alarm Output
Alarm Output No.	A->1	
Alarm Name	test	
Dwell Time	5s	
Handling	⚙️	

Figure 8.17 Alarm Output Settings Interface

- Set arming schedule of the alarm output.

Click  to set the arming schedule of alarm output. Choose one day of a week and up to 8 time periods can be set within each day.

**Note:** Time periods shall not be repeated or overlapped.

Handling	
Arming Schedule	
Week	Mon
1	00:00-24:00
2	00:00-00:00
3	00:00-00:00
4	00:00-00:00
5	00:00-00:00
6	00:00-00:00
7	00:00-00:00
8	00:00-00:00

Copy Apply OK Cancel

Figure 8.18 Set Arming Schedule of Alarm Output

- Repeat the above steps to set up arming schedule of other days of a week. You can also click **Copy** to copy an arming schedule to other days. Click **OK** to complete the settings of the alarm output.
- You can also click **Copy** in Alarm Output interface to copy the above settings to another channel.

Copy Alarm Output to		
Alarm Output No.	Alarm Name	IP Camera Address
<input checked="" type="checkbox"/> A->1		Local
<input type="checkbox"/> A->2		Local
<input type="checkbox"/> A->3		Local
<input type="checkbox"/> A->4		Local

OK Cancel

Figure 8.19 Copy Settings of Alarm Output



## 8.7 Triggering or Clearing Alarm Output Manually

**Note:** This section is available for DS-7300HWI/HFI-SH models only.

**Purpose:**

Sensor alarm can be triggered or cleared manually. If **Manually Clear** is selected in the dropdown list of dwell time of an alarm output, the alarm can be cleared only by clicking **Clear** button in the following interface.

**Steps:**


Select the alarm output you want to trigger or clear and make related operations.

Menu> Manual> Alarm

Click **Trigger** / **Clear** button if you want to trigger or clear an alarm output.

Click **Trigger All** button if you want to trigger all alarm outputs.

Click **Clear All** button if you want to clear all alarm output.



No.	Alarm Name	IP Camera Address	Trigger
A->1		Local	No
A->2		Local	No
A->3		Local	No
A->4		Local	No

Figure 8.20 Clear or Trigger Alarm Output Manually

---

# **C H A P T E R 9**

## **Network Settings**

## 9.1 Configuring General Settings

### Purpose:

Network settings must be properly configured before you operate device over network.

### Steps:

1. Enter the Network Settings interface.

Menu > Configuration > Network

General	PPPOE	DDNS	NTP	Email	SNMP	UPnP	More Settings
NIC Type	10M/100M Self-adaptive						
Enable DHCP	<input type="checkbox"/>						
IPv4 Address	172 . 6 . 21 . 64						
IPv4 Subnet Mask	255 . 255 . 255 . 0						
IPv4 Default Gateway	172 . 6 . 21 . 1						
IPv6 Address 1	fe80::240:48ff:fe90:cf13/64						
IPv6 Address 2							
IPv6 Default Gateway							
MAC Address	00:40:48:90:cf:13						
MTU(Bytes)	1500						
Preferred DNS Server							
Alternate DNS Server							

Figure 9.1 General Network Settings of DS-7200-SH/SV

General	PPPOE	DDNS	NTP	Email	SNMP	UPnP	More Settings
NIC Type	10M/100M/1000M Self-adaptive						
Enable DHCP	<input type="checkbox"/>						
IPv4 Address	172 . 6 . 21 . 64						
IPv4 Subnet Mask	255 . 255 . 255 . 0						
IPv4 Default Gateway	172 . 6 . 21 . 1						
IPv6 Address 1	fe80::240:48ff:fe90:cf13/64						
IPv6 Address 2							
IPv6 Default Gateway							
MAC Address	00:40:48:90:cf:13						
MTU(Bytes)	1500						
Preferred DNS Server							
Alternate DNS Server							

Figure 9.2 General Network Settings of DS-7300HWI/HFI-SH

2. Select the **General** tab.
3. In the **General Settings** interface:

You can configure the following settings: NIC Type, IPv4 Address, IPv4 Gateway, MTU and DNS Server.

**Note:** The DS-7200-SH/SV models provide one 10M/100Mbps self-adaptive network interface, and the DS-7300HWI/HFI-SH models provide one 10M/100M/1000Mbps self-adaptive network interface.

If the DHCP server is available, you can click the checkbox of **DHCP** to automatically obtain an IP address and other network settings from that server.

**Note:** The valid value range of MTU is 500 ~ 1500.

4. After having configured the general settings, click the **Apply** button to save the settings.

## 9.2 Configuring Advanced Settings

### 9.2.1 Configuring PPPoE Settings

**Purpose:**

Your device also allows access by Point-to-Point Protocol over Ethernet (PPPoE).

**Steps:**

1. Enter the **Network Settings** interface.  
Menu > Configuration > Network
2. Select the **PPPoE** tab to enter the PPPoE Settings interface.

Enable PPPOE	<input type="checkbox"/>
User Name	
Password	

Figure 9.3 PPPoE Settings Interface

3. Check the **PPPoE** checkbox to enable this feature.
4. Enter **User Name** and **Password** for PPPoE access.

**Note:** The User Name and Password should be assigned by your ISP.

Enable PPPOE	<input checked="" type="checkbox"/>
User Name	test
Password	*****

Figure 9.4 PPPoE Settings Interface

5. Click the **Apply** button to save and exit the interface.
6. After successful settings, the system asks you to reboot the device to enable the new settings, and the PPPoE dial-up is automatically connected after reboot.  
You can go to Menu>Maintenance>System Info>Network interface to view the status of PPPoE connection. Please refer to *Chapter 12. Viewing System Information* for PPPoE status.

### 9.2.2 Configuring DDNS

**Purpose:**

If your device is set to use PPPoE as its default network connection, you may set Dynamic DNS (DDNS) to be used for network access.

Prior registration with your ISP is required before configuring the system to use DDNS.

**Steps:**

1. Enter the Network Settings interface.  
Menu > Configuration > Network
2. Select the **DDNS** tab to enter the DDNS Settings interface.

Enable DDNS	<input checked="" type="checkbox"/>
DDNS Type	IPServer
Server Address	
Device Domain Name	
User Name	
Password	

Figure 9.5 DDNS Settings Interface

3. Check the **DDNS** checkbox to enable this feature.
4. Select **DDNS Type**. Five different DDNS types are selectable: IPSever, DynDNS, PeanutHull, NO-IP and hkDDNS.

- **IPSever:** Enter **Server Address** for IPSever.

**Note:** The **Server Address** should be the IP address of the PC that runs IPSever.

Enable DDNS	<input checked="" type="checkbox"/>
DDNS Type	IPSever
Server Address	172.5.22.122
Device Domain Name	
User Name	
Password	

Figure 9.6 IPSever Settings Interface

- **DynDNS:**

- 1) Enter **Server Address** for DynDNS (e.g. members.dyndns.org).
- 2) In the **Device Domain Name** text field, enter the domain obtained from the DynDNS website.
- 3) Enter the **User Name** and **Password** registered in the DynDNS website.

Enable DDNS	<input checked="" type="checkbox"/>
DDNS Type	DynDNS
Server Address	members.dyndns.org
Device Domain Name	123.dyndns.com
User Name	test
Password	*****

Figure 9.7 DynDNS Settings Interface

- **PeanutHull:** Enter User Name and Password obtained from the PeanutHull website.

Enable DDNS	<input checked="" type="checkbox"/>
DDNS Type	PeanutHull
Server Address	
Device Domain Name	
User Name	123.gicp.net
Password	*****
Confirm	*****

Figure 9.8 Peanut Hull Settings Interface

- **NO-IP:**

Enter the account information in the corresponding fields. Refer to the DynDNS settings.

- 1) Enter **Server Address** for NO-IP.
- 2) In the **Device Domain Name** text field, enter the domain obtained from the NO-IP website (www.no-ip.com).
- 3) Enter the **User Name** and **Password** registered in the NO-IP website.

Enable DDNS	<input checked="" type="checkbox"/>
DDNS Type	NO-IP
Server Address	no-ip.org
Device Domain Name	123.no-ip.org
User Name	test
Password	*****

Figure 9.9 NO-IP Settings Interface

- **hkDDNS:** You need to enter the **Server Address** and **Device Domain Name** for hkDDNS, and other fields are read only.


- 1) Enter the **Server Address** of the hkDDNS server: www.hik-online.com.
- 2) Enter the **Device Domain Name**. You can register the alias of the device domain name in the hkDDNS server first and then enter the alias to the **Device Domain Name** in the DVR; you can also enter the domain name directly on the DVR to create a new one.

**Note:** If a new alias of the device domain name is defined in the DVR, it will replace the old one registered on the server.

Enable DDNS	<input checked="" type="checkbox"/>
DDNS Type	hkDDNS
Server Address	www.hik-online.com
Device Domain Name	test
User Name	

Figure 9.10 hkDDNS Settings Interface

**Register the device on the hkDDNS server.**

- 1) Go to the hkDDNS website: [www.hik-online.com](http://www.hik-online.com).
- 2) Click  to register a user account if you do not have one.
- 3) After registration is successful, use the account and password to log in.



4. Configure the following NTP settings:
  - **Interval:** Time interval between the two synchronizing actions with NTP server. The unit is minute.
  - **NTP Server:** IP address of NTP server.
  - **NTP Port:** Port of NTP server.
5. Click the **Apply** button to save and exit the interface.

**Note:** The time synchronization interval can be set from 1 to 10080min, and the default value is 60min. If the device is connected to a public network, you should use a NTP server that has a time synchronization function, such as the server at the National Time Center (IP Address: 210.72.145.44). If the device is setup in a more customized network, NTP software can be used to establish a NTP server used for time synchronization.

## 9.2.4 Configuring SNMP

### *Purpose:*

You can use SNMP protocol to get device status and parameters related information.

### *Steps:*

1. Enter the Network Settings interface.  
Menu > Configuration > Network
2. Select the **SNMP** tab to enter the SNMP Settings interface.

Enable SNMP	<input type="checkbox"/>
SNMP Version	V2
SNMP Port	161
Read Community	public
Write Community	private
Trap Address	
Trap Port	162

Figure 9.14 SNMP Settings Interface

3. Check the **SNMP** checkbox to enable this feature.
4. Configure the SNMP settings.

Enable SNMP	<input checked="" type="checkbox"/>
SNMP Version	V2
SNMP Port	161
Read Community	public
Write Community	private
Trap Address	
Trap Port	162

Figure 9.15 Configure SNMP Settings

5. Click the **Apply** button to save and exit the interface.

**Note:** Before setting the SNMP, please download the SNMP software and manage to receive the device information via SNMP port. By setting the Trap Address, the device is allowed to send the alarm event and exception message to the surveillance center.



## 9.2.5 Configuring UPnP™

### Purpose:

UPnP™ can permits the device seamlessly discover the presence of other network devices on the network and establish functional network services for data sharing, communications, etc. If you want to use the UPnP™ function to enable the fast connection of the device to the WAN via a router, you should configure the UPnP™ parameters of the device.

### Before you start:

If you want to enable the UPnP™ function of the device, you must enable the UPnP™ function of the router to which your device is connected. When the network working mode of the device is set as multi-address, the Default Route of the device should be in the same network segment as that of the LAN IP address of the router.

### Steps:

1. Enter the Network Settings interface.  
Menu > Configuration > Network
2. Select the **UPnP™** tab to enter the UPnP™ interface.

Port Type	Edit	External P...	Mapping IP Address	Port	Status
Server Port		8000	0.0.0.0	8000	Inactive
HTTP Port		80	0.0.0.0	80	Inactive
RTSP Port		554	0.0.0.0	554	Inactive

Figure 9.16 UPnP™ Settings Interface

3. Check ☒ checkbox to enable UPnP™.
4. Select the mapped type to Auto or Manual.  
When you select **Auto**, the mapping ports can be automatically assigned by the router. When you select **Manual**, you should continue Step5 to edit the mapping ports.
5. Click to open the External Port Settings dialog box. Configure the external port No. for server port, HTTP port and RTSP port respectively.

### Notes:

- 1) You can use the default port No., or change it according to actual requirements.
- 2) External Port indicates the port No. for port mapping in the router.

Figure 9.17 External Port Settings Dialog Box

6. You can click **Refresh** to get the latest status of the port mapping.

Enable UPnP	<input checked="" type="checkbox"/>				
Mapping Type	Auto				
Port Type	Edit	External P...	Mapping IP Address	Port	Status
Server Port		8000	172.6.21.31	8000	Active
HTTP Port		80	172.6.21.31	80	Active
RTSP Port		554	172.6.21.31	554	Active
Refresh					

Figure 9.18 UPnP Settings Finished

7. Click the **Apply** button to save the settings.

## 9.2.6 Configuring Remote Alarm Host

### *Purpose:*

With a remote alarm host configured, the device will send the alarm event or exception message to the host when an alarm is triggered. The remote alarm host must have the CMS (Client Management System) software installed.

### *Steps:*

1. Enter the Network Settings interface.  
Menu > Configuration > Network
2. Select the **More Settings** tab to enter the More Settings interface.

Alarm Host IP	
Alarm Host Port	0
Server Port	8000
HTTP Port	80
Multicast IP	
RTSP Port	554

Figure 9.19 More Settings Interface

3. Enter **Alarm Host IP** and **Alarm Host Port** in the text fields.

The **Alarm Host IP** refers to the IP address of the remote PC on which the CMS (Client Management System) software (e.g., iVMS-4200) is installed, and the **Alarm Host Port** must be the same as the alarm monitoring port configured in the software (default port is 7200).

Alarm Host IP	172.5.8.111
Alarm Host Port	7200
Server Port	8000
HTTP Port	80
Multicast IP	
RTSP Port	554

Figure 9.20 Configure Alarm Host

4. Click the **Apply** button to save and exit the interface.

## 9.2.7 Configuring Multicast

### *Purpose:*

The multicast can be configured to realize live view for more than the maximum number of cameras through network.

A multicast address spans the Class-D IP range of 224.0.0.0 to 239.255.255.255. It is recommended to use the IP address ranging from 239.252.0.0 to 239.255.255.255.

### *Steps:*

1. Enter the Network Settings interface.  
Menu > Configuration > Network
2. Select the **More Settings** tab to enter the More Settings interface.
3. Set **Multicast IP**. When adding a device to the CMS (Client Management System) software, the multicast address must be the same as the device's multicast IP.

Alarm Host IP	172.5.8.111
Alarm Host Port	7200
Server Port	8000
HTTP Port	80
Multicast IP	239.252.2.50
RTSP Port	554

Figure 9.21 Configure Multicast

4. Click the **Apply** button to save and exit the interface.

## 9.2.8 Configuring RTSP

### *Purpose:*

The RTSP (Real Time Streaming Protocol) is a network control protocol designed for use in entertainment and communications systems to control streaming media servers.

### *Steps:*

1. Enter the Network Settings menu by clicking Menu > Configuration > Network.
2. Select the **More Settings** tab to enter the More Settings men.

Alarm Host IP	172.5.8.111
Alarm Host Port	7200
Server Port	8000
HTTP Port	80
Multicast IP	239.252.2.50
RTSP Port	554

Figure 9.22 RTSP Settings Interface

3. Enter the RTSP port in the text field of **RTSP Service Port**. The default RTSP port is 554, and you can change it according to different requirements.

- Click the **Apply** button to save and exit the menu.

## 9.2.9 Configuring Server and HTTP Ports

### *Purpose:*

You can change the server and HTTP ports in the Network Settings menu. The default server port is 8000 and the default HTTP port is 80.

### *Steps:*

- Enter the Network Settings interface.  
Menu > Configuration > Network
- Select the **More Settings** tab to enter the More Settings interface.
- Enter new **Server Port** and **HTTP Port**.

Alarm Host IP	
Alarm Host Port	
Server Port	8000
HTTP Port	80
Multicast IP	
RTSP Port	

Figure 9.23 Host/Others Settings Menu

- Enter the Server Port and HTTP Port in the text fields. The default Server Port is 8000 and the HTTP Port is 80, and you can change them according to different requirements.
- Click the **Apply** button to save and exit the interface.

**Note:** The Server Port should be set to the range of 2000-65535 and it is used for remote client software access. The HTTP port is used for remote IE access.

## 9.2.10 Configuring Email

### *Purpose:*

The system can be configured to send an Email notification to all designated users if an alarm event is detected, a motion detection event is detected, etc.

Before configuring the Email settings, the device must be connected to a local area network (LAN) that maintains an SMTP mail server. The network must also be connected to either an intranet or the Internet depending on the location of the e-mail accounts to which you want to send notification.

### *Steps:*

- Enter the Network Settings interface.  
Menu > Configuration > Network
- Set the IPv4 Address, IPv4 Subnet Mask, IPv4 Gateway and the Preferred DNS Server in the Network Settings menu.

General	PPPOE	DDNS	NTP	Email	SNMP	UPnP	More Settings
NIC Type	10M/100M Self-adaptive						
Enable DHCP	<input type="checkbox"/>						
IPv4 Address	172 .6 .21 .64						
IPv4 Subnet Mask	255 .255 .255 .0						
IPv4 Default Gateway	172 .6 .21 .1						
IPv6 Address 1	fe80::240:48ff:fe90:cf13/64						
IPv6 Address 2							
IPv6 Default Gateway							
MAC Address	00:40:48:90:cf:13						
MTU(Bytes)	1500						
Preferred DNS Server	192.0.0.200						
Alternate DNS Server							

Figure 9.24 Network Settings Interface

- Click the **Apply** button to save the settings.
- Select the **Email** tab to enter the Email Settings interface.

Enable Server Authentica...	<input type="checkbox"/>
User Name	
Password	
SMTP Server	
SMTP Port	25
Enable SSL	<input type="checkbox"/>
Sender	
Sender's Address	
Select Receivers	Receiver 1
Receiver	
Receiver's Address	
Enable Attached Picture	<input type="checkbox"/>
Interval	2s

Figure 9.25 Email Settings Interface

- Configure the following Email settings:

**Enable Server Authentication (optional):** Check the checkbox to enable the server authentication feature.

**User Name:** The user account of sender's Email for SMTP server authentication.

**Password:** The password of sender's Email for SMTP server authentication.

**SMTP Server:** The SMTP Server IP address or host name (e.g., smtp.263xmail.com).

**SMTP Port:** The SMTP port. The default TCP/IP port used for SMTP is 25.

**Enable SSL (optional):** Click the checkbox to enable SSL if required by the SMTP server.

**Sender:** The name of sender.

**Sender's Address:** The Email address of sender.

**Select Receivers:** Select the receiver. Up to 3 receivers can be configured.

**Receiver:** The name of user to be notified.

**Receiver's Address:** The Email address of user to be notified.

**Enable Attached Pictures:** Check the checkbox of **Enable Attached Picture** if you want to send email with attached alarm images.

**Interval:** The interval refers to the time between two actions of sending attached pictures.

Enable Server Authentica...	<input type="checkbox"/>
User Name	
Password	
SMTP Server	126.smtp.com
SMTP Port	25
Enable SSL	<input checked="" type="checkbox"/>
Sender	test01
Sender's Address	test01@126.com
Select Receivers	Receiver 1
Receiver	test02
Receiver's Address	test02@163.com
Enable Attached Picture	<input checked="" type="checkbox"/>
Interval	2s

Figure 9.26 Configure Email Settings

---

6. Click the **Apply** button to save the Email settings.
7. You can click the **Test** button to test whether your Email settings work. The corresponding Attention message box will pop up.




Figure 9.27 Email Testing Attention

---

## 9.3 Checking Network Traffic

### *Purpose:*

You can check the network traffic to obtain real-time information of device such as linking status, MTU, sending/receiving rate, etc.

### *Steps:*

1. Enter the Network Traffic interface.

Menu > Maintenance > Net Detect




Figure 9.28 Network Traffic Interface

2. You can view the sending rate and receiving rate information on the interface. The traffic data is refreshed every 1 second.

## 9.4 Network Detection

### Purpose:

You can obtain network connecting status of device through the network detection function, including network delay, packet loss, etc.

### 9.4.1 Testing Network Delay and Packet Loss

#### Steps:

1. Enter the Network Traffic interface.  
Menu > Maintenance > Net Detect
2. Click the **Network Detection** tab to enter the Network Detection menu.




Figure 9.29 Network Detection Interface

3. Enter the destination address in the text field of **Destination Address**.
4. Click the **Test** button to start testing network delay and packet loss. The testing result pops up on the window. If the testing is failed, the error message box will pop up as well.




Figure 9.30 Testing Result of Network Delay and Packet Loss

### 9.4.2 Exporting Network Packet

#### Purpose:

By connecting the device to network, the captured network data packet can be exported to USB-flash disk and other local backup devices.

#### Steps:

1. Enter the Network Traffic interface.  
Menu > Maintenance > Net Detect
2. Click the **Network Detection** tab to enter the Network Detection interface.



3. Select the backup device from the dropdown list of Device Name, as shown in Figure 9.30.

**Note:** Click the **Refresh** button if the connected local backup device cannot be displayed. When it fails to detect the backup device, please check whether it is compatible with the device. You can format the backup device if the format is incorrect.




Figure 9.31 Export Network Packet

4. Click the **Export** button to start exporting.
5. After the exporting is complete, click **OK** to finish the packet export.



Figure 9.32 Packet Export Attention

**Note:** Up to 1M data can be exported each time.

### 9.4.3 Checking Network Status

**Purpose:**

You can also check the network status and quick set the network parameters in this interface.

**Steps:**

- Click **Status** on the right bottom of the page.




Figure 9.33 Checking Network Status

If the network is normal the following message box pops out.




Figure 9.34 Network Status Checking Result

If the message box pops out with other information instead of this one, you can click **Network** button to show the quick setting interface of the network parameters.




Figure 9.35 Network Parameters Configuration


## 9.4.4 Checking Network Statistics

### *Purpose:*

You can check the network statistics to obtain the real-time information of the device.

### *Steps:*

1. Enter the Network Statistics interface.  
Menu > Maintenance> Net Detect
2. Click the **Network Stat.** tab to enter the Network Statistics menu.



The screenshot shows a web interface with three tabs: 'Traffic', 'Network Detection', and 'Network Stat.'. The 'Network Stat.' tab is selected and underlined. Below the tabs is a table with two columns: 'Type' and 'Bandwidth'. The table contains three rows of data. At the bottom right of the interface is a 'Refresh' button.

Type	Bandwidth
Remote Live View	0bps
Remote Playback	0bps
Net Total Idle	60Mbps

Refresh

Figure 9.36 Network Stat. Interface

3. View the bandwidth of Remote Live View, bandwidth of Remote Playback, bandwidth of Net Total Idle information.
4. Click **Refresh** button to get the latest bandwidth statistics.

# CHAPTER 10

## HDD Management

## 10.1 Initializing HDDs

### *Purpose:*

A newly installed hard disk drive (HDD) must be initialized before it can be used with your device.

### *Steps:*

1. Enter the HDD Information interface.

Menu > HDD>General




Figure 10.1 HDD Information Interface

2. Select the HDD to be initialized.
3. Click the **Init** button.




Figure 10.2 Confirm Initialization

4. Select the **OK** button to start initialization.




Figure 10.3 Start Initialization

5. After the HDD has been initialized, the status of the HDD will change from *Uninitialized* to *Normal*.

**HDD Information**

<input type="checkbox"/> L...	Capacity	Status	Property	Type	Free Space	Gr...	Edit	D...
<input type="checkbox"/> 1	931.51GB	Normal	R/W	Local	927GB	1		-

Figure 10.4 HDD Status Changes to Normal

**Note:** Initializing the HDD will erase all data on it.

## 10.2 Managing Network HDD

### *Purpose:*

You can add the allocated NAS or disk of IP SAN to device, and use it as network HDD.

### *Steps:*

1. Enter the HDD Information interface.

Menu > HDD > General




Figure 10.5 HDD Information Interface

2. Click the **Add** button to enter the Add NetHDD interface, as shown in Figure 10.6.




Figure 10.6 Adding NetHDD Interface

3. Add the allocated NetHDD.
4. Select the type to NAS or IP SAN.



**Note:** If the added NetHDD is uninitialized, please select it and click the **Init** button for initialization.

HDD Information




<input type="checkbox"/> L...	Capacity	Status	Property	Type	Free Space	Gr...	Edit	D...
<input checked="" type="checkbox"/> 1	931.51GB	Normal	R/W	Local	906GB	1		—
<input checked="" type="checkbox"/> 17	40,000MB	Normal	R/W	IP SAN	22,528MB	1		

Figure 10.9 Initialize Added NetHDD

---



## 10.3 Managing HDD Group

### 10.3.1 Setting HDD Groups

**Purpose:**

Multiple HDDs can be managed in groups. Video from specified channels can be recorded onto a particular HDD group through HDD settings.

**Steps:**

1. Enter the Storage Mode interface.  
Menu > HDD > Advanced
2. Set the **Mode** to Group, as shown below:




Figure 10.10 Storage Mode Interface

3. Click the **Apply** button and the following Attention box will pop up.





Figure 10.11 Attention for Reboot

4. Click the **Yes** button to reboot the device to activate the changes.
5. After reboot of device, enter the HDD Information interface.  
Menu > HDD > General
6. Select HDD from the list and click the  icon to enter the Local HDD Settings interface.




Figure 10.12 Local HDD Settings Interface

7. Select the Group number for the current HDD.

**Note:** The default group No. for each HDD is 1.

8. Click the **OK** button to confirm the settings.



Figure 10.13 Confirm HDD Group Settings

9. In the pop-up Attention box, click the **Yes** button to finish the settings.

## 10.3.2 Setting HDD Property

### **Purpose:**

The HDD property can be set to redundancy, read-only or read/write (R/W). Before setting the HDD property, please set the storage mode to Group (refer to step1-4 of *Chapter 10.3.1 Setting HDD Groups*).

A HDD can be set to read-only to prevent important recorded files from being overwritten when the HDD becomes full in overwrite recording mode.

When the HDD property is set to redundancy, the video can be recorded both onto the redundancy HDD and the R/W HDD simultaneously so as to ensure high security and reliability of video data.

### **Steps:**


1. Enter the HDD Information interface.  
Menu > HDD > General
2. Select HDD from the list and click the  icon to enter the Local HDD Settings interface.



Figure 10.14 Set HDD Property

3. Set the HDD property to R/W, Read-only or Redundancy.
4. Click the **OK** button to save the settings and exit the interface.
5. In the HDD Information menu, the HDD property will be displayed in the list.

**Note:** At least 2 hard disks must be installed on your device when you want to set a HDD to Redundancy, and there is one HDD with R/W property.

## 10.4 Configuring Quota Mode

### Purpose

Each camera can be configured with allocated quota for the storage of recorded files.

### Steps

1. Enter the Storage Mode interface.

Menu > HDD > Advanced

2. Set the **Mode** to **Quota**.

**Note:** The device must be rebooted to enable the changes to take effect.




Figure 10.15 Storage Mode Settings Interface

3. Enter the storage capacity in the text field of **Max. Record Capacity (GB)**.




Figure 10.16 Configure Record Quota

4. You can copy the quota settings of the current camera to other cameras if required. Click the **Copy** button to enter the Copy Camera menu, as shown below.




Figure 10.17 Copy Settings to Other Camera(s)

5. Select the camera (s) to be configured with the same quota settings. You can also click the checkbox of

**Analog** to select all cameras.

6. Click the **OK** button to finish the Copy settings and back to the Storage Mode interface.
7. Click the **Apply** button to apply the settings.

**Note:** If the quota capacity is set to 0, then all cameras will use the total capacity of HDD for recording.

## 10.5 Checking HDD Status


### *Purpose:*

You may check the status of the installed HDDs on device so as to take immediate check and maintenance in case of HDD failure.

### Checking HDD Status in HDD Information Interface

#### *Steps:*

1. Enter the HDD Information interface.  
Menu > HDD>General
2. Check the status of each HDD which is displayed on the list.



HDD Information								
<input type="checkbox"/> L...	Capacity	Status	Property	Type	Free Space	Gr...	Edit	D...
<input type="checkbox"/> 1	931.51GB	Normal	R/W	Local	927GB	1		—


Figure 10.18 View HDD Status (1)

**Note:** If the status of HDD is *Normal* or *Sleeping*, it works normally. If the status is *Uninitialized* or *Abnormal*, please initialize the HDD before use. And if the HDD initialization is failed, please replace it with a new one.

### Checking HDD Status in HDD Information Interface

#### *Steps:*

1. Enter the System Information interface.  
Menu > Maintenance > System Info
2. Click the **HDD** tab to view the status of HDD displayed on the list.



Device Info   Camera   Record   Network <u>HDD</u>						
Label	Status	Capacity	Free Space	Property	Type	Group
5	Normal	931.51GB	927GB	R/W	Local	1

Total Capacity	931.51GB
Free Space	927GB

Figure 10.19 View HDD Status (2)

## 10.6 Checking S.M.A.R.T. Information

### Purpose:

The S.M.A.R.T. (Self-Monitoring, Analysis and Reporting Technology) is a monitoring system for HDD to detect and report on various indicators of reliability in the hopes of anticipating failures.

### Steps:


1. Enter the S.M.A.R.T. Settings interface.

Menu > HDD > HDD Detect > S.M.A.R.T. Settings

2. Select the HDD to view its S.M.A.R.T. information list.

**Note:** If you want to use the HDD even when the S.M.A.R.T. checking is failed, you can check the checkbox before the **Continue to use this disk when self-evaluation is failed** item.

3. Three self-tests of S.M.A.R.T are provided, including Short Test, Expanded Test and Conveyance Test.

You can select a self-test type and click  to start self-test.


**S.M.A.R.T. Settings** Bad Sector Detection

☐ Continue to use this disk when self-evaluation is failed.

HDD: 1

Self-test Status: Self-test successful

Self-test Type: Short Test

S.M.A.R.T. 

Temperature (°C): 33

Power On (days): 185

Self-evaluation: Pass

All-evaluation: Functional

**S.M.A.R.T. Information**

ID	Attribute Name	Status	Flags	Thresh...	Value	Worst	Raw Value
0x1	Raw Read Error Rate	OK	2f	51	200	200	418
0x3	Spin Up Time	OK	27	21	132	107	6366
0x4	Start/Stop Count	OK	32	0	100	100	294
0x5	Reallocated Sector Co...	OK	33	140	200	200	0
0x7	Seek Error Rate	OK	2e	0	200	200	0
0x9	Power-on Hours Count	OK	32	0	94	94	4452
0xa	Spin Up Retry Count	OK	32	0	100	100	0

Figure 10.20 S.M.A.R.T. Settings Interface

## 10.7 Detecting Bad Sector

### *Purpose:*

The bad sectors of a HDD may cause the system to slow down when reading or writing data. You can detect the bad sectors of the HDD and thus to take immediate measures to repair it.

### *Steps:*

1. Enter the Bad Sector Detection interface.

Menu>HDD>HDD Detect>Bad Sector Detection




Figure 10.21 Bad Sector Detection

2. Select a HDD and click **Detect** to start detecting.




Figure 10.22 Bad Sector Detecting

3. You can click **Pause** to pause the detection and click **Resume** to resume the detection.
4. If there is any error information about the HDD, you can click **Error info** to view the information.



## 10.8 Configuring HDD Error Alarms

### *Purpose:*

You can configure the HDD error alarms when the HDD status is *Uninitialized* or *Abnormal*.

### *Steps:*

1. Enter the Exception interface.  
Menu > Configuration > Exceptions
2. Select the Exception Type to **HDD Error** from the dropdown list.
3. Click the checkbox(s) below to select the HDD error alarm type (s).

**Note:** The alarm type can be selected to: Audio Warning, Notify Surveillance Center, and Send Email. Please refer to *Chapter 8.5 Setting Alarm Response Actions*.



Figure 10.23 Configure HDD Error Alarm

4. Click the **Apply** button to save the settings.

# **C H A P T E R 11**

## **Camera Settings**

## 11.1 Configuring OSD Settings

### Purpose:

You can configure the OSD (On-screen Display) settings for the camera, including date /time, camera name, etc.

### Steps:

1. Enter the OSD Configuration interface.  
Menu > Camera > OSD
2. Select the camera to configure OSD settings.
3. Edit the Camera Name in the text field.
4. Configure the Display Name, Display Date and Display Week by clicking the checkbox.
5. Select the Date Format, Time Format and Display Mode.




Figure 11.1 OSD Configuration Interface

6. You can use the mouse to click and drag the text frame on the preview window to adjust the OSD position.
7. Copy Camera Settings
  - 1) If you want to copy the OSD settings of the current camera to other cameras, click the **Copy** button to enter the Copy Camera interface, as shown in Figure 11.2.




Figure 11.2 Copy Settings to Other Cameras

- 2) Select the camera (s) to be configured with the same OSD settings. You can also click the checkbox of Analog to select all cameras.
- 3) Click the **OK** button to finish the Copy settings and back to the OSD Configuration interface.
8. Click the **Apply** button to apply the settings.

**Note:** You can also click the **Restore** to restore the current OSD settings to the default parameters.

## 11.2 Configuring Privacy Mask

### Purpose:

You are allowed to configure the four-sided privacy mask zones that cannot be viewed by the operator.

### Steps:

1. Enter the Privacy Mask Settings interface.  
Menu > Camera > Privacy Mask
2. Select the camera to set privacy mask.
3. Click the checkbox of **Enable Privacy Mask** to enable this feature.



Figure 11.3 Privacy Mask Settings Interface

4. Use the mouse to draw a zone on the window. The zones will be marked with different frame colors.
- Note:** Up to 4 privacy mask zones can be configured, and the size of each area can be adjusted.
5. The configured privacy mask zones on the window can be cleared by clicking the corresponding Clear Zone1-4 icons on the right side of the window, or click **Clear All** to clear all zones.



Figure 11.4 Set Privacy Mask Area

6. You can click the **Copy** button to copy the privacy mask settings of the current camera to other cameras.  
Please refer to step 7 of *Chapter 11.1 Configuring OSD Settings*.
7. Click the **Apply** button to save the settings.

**Note:** You can also click the **Restore** to restore the current OSD settings to the default parameters.

## 11.3 Configuring Video Parameters

### Steps:

1. Enter the Image Settings interface.  
Menu > Camera > Image
2. Select the camera to set image parameters.
3. Set the period of a day for configuring independent image parameters so as to satisfy different light conditions, e.g., daylight and night time. Two periods can be configured. When you have configured Period 1, the Period 2 is remained as the *Other Time*.



Figure 11.5 Image Settings Interface

4. Select the mode from the drop-down menu according to different light conditions.  
Four modes are selectable:
  - **Standard:** in general lighting conditions (default).
  - **Indoor:** the image is relatively smoother.
  - **Dim Light:** the image is smoother than the other three modes.
  - **Outdoor:** the image is relatively clearer and sharper. The degree of contrast and saturation is high.
5. Adjust the image parameters including the brightness, contrast, saturation, hue, sharpness and denoising level by moving the sliding bar or increasing/decreasing the value.  
**Note:** When you select different mode, corresponding default parameters are available. You can also adjust the value of the brightness, contrast, saturation and hue to 0~ 255, the sharpness to 0~ 15 and the denoising level to 0~ 5.
6. You can click the **Copy** button to copy the image settings of the current camera to other cameras. Please refer to step 7 of *Chapter 11.1 Configuring OSD Settings*.
7. On the Image Settings interface, click the **Apply** button to save the settings.

**Note:** you can click the **Restore** button to restore the current image settings to default parameters.

# **C H A P T E R 1 2**

## **Device Management and Maintenance**

## 12.1 Viewing System Information

### 12.1.1 Viewing Device Information

*Steps:*

1. Enter the System Information interface.  
Menu > Maintenance > System Info
2. Click the **Device Info** tab to enter the Device Information menu to view the device name, model, serial No. ,  
firmware version and encoding version.

<u>Device Info</u>	Camera	Record	Network	HDD
Device Name	Embedded Net DVR			
Model	DS-7216HWI-SH			
Serial No.	1620121025AAWR201210134WCVU			
Firmware Version	V0.0.0, Build 000000			
Encoding Version	V0.0, Build 000000			

Figure 12.1 Device Information Interface

### 12.1.2 Viewing Camera Information

*Steps:*

1. Enter the System Information interface.  
Menu > Maintenance > System Info
2. Click the **Camera** tab to enter the Camera Information menu to view the status of each camera.

Device Info	Camera	Record	Alarm	Network	HDD	
Camera...	Camera Name	Status	Motion Det...	Tampe...	Video Loss	Video
A1	Camera 01	Enabled	Used	Not used	Not used	Used
A2	Camera 02	Enabled	Used	Not used	Not used	Used
A3	Camera 03	Enabled	Used	Not used	Not used	Used
A4	Camera 04	Enabled	Used	Not used	Not used	Used
A5	Camera 05	Enabled	Used	Not used	Not used	Used
A6	Camera 06	Enabled	Used	Not used	Not used	Used
A7	Camera 07	Enabled	Used	Not used	Not used	Used
A8	Camera 08	Enabled	Used	Not used	Not used	Used
A9	Camera 09	Enabled	Used	Not used	Not used	Used
A10	Camera 10	Enabled	Used	Not used	Not used	Used
A11	Camera 11	Enabled	Used	Not used	Not used	Used
A12	Camera 12	Enabled	Used	Not used	Not used	Used
A13	Camera 13	Enabled	Used	Not used	Not used	Used
A14	Camera 14	Enabled	Used	Not used	Not used	Used
A15	Camera 15	Enabled	Used	Not used	Not used	Used
A16	Camera 16	Enabled	Used	Not used	Not used	Used

Figure 12.2 Camera Information Interface

### 12.1.3 Viewing Record Information

*Steps:*

1. Enter the System Information interface.  
Menu > Maintenance > System Info
2. Click the **Record** tab to enter the Record Information menu to view the recording status and encoding parameters of each camera.

Device Info	Camera	Record	Alarm	Network	HDD			
Camer...	Record...	Stream...	Frame ...	Bitrate(Kbps)	Resolution	Record...	Encodi...	Redun...
A1	Used	Video ...	25fps	81/1792	704*576(4...	Manual	Event	No
A2	Not used	Video ...	25fps	84/1792	704*576(4...		Event	No
A3	Not used	Video ...	25fps	85/1792	704*576(4...		Event	No
A4	Not used	Video ...	25fps	83/1792	704*576(4...		Normal	No
A5	Not used	Video ...	25fps	83/1792	704*576(4...		Normal	No
A6	Not used	Video ...	25fps	85/1792	704*576(4...		Normal	No
A7	Not used	Video ...	25fps	85/1792	704*576(4...		Normal	No
A8	Not used	Video ...	25fps	84/1792	704*576(4...		Normal	No
A9	Not used	Video ...	25fps	85/1792	704*576(4...		Normal	No
A10	Not used	Video ...	25fps	85/1792	704*576(4...		Normal	No
A11	Not used	Video ...	25fps	83/1792	704*576(4...		Normal	No
A12	Not used	Video ...	25fps	83/1792	704*576(4...		Normal	No
A13	Not used	Video ...	25fps	84/1792	704*576(4...		Normal	No
A14	Not used	Video ...	25fps	83/1792	704*576(4...		Normal	No
A15	Not used	Video ...	25fps	82/1792	704*576(4...		Normal	No
A16	Not used	Video ...	25fps	85/1792	704*576(4...		Normal	No

Figure 12.3 Record Information Interface

### 12.1.4 Viewing Network Information

*Steps:*

1. Enter the System Information interface.  
Menu > Maintenance > System Info
2. Click the **Network** tab to enter the Network Information menu to view the network information.

Device Info	Camera	Record	Network	HDD
NIC		LAN1		
IPv4 Address		172.6.24.64		
IPv4 Subnet Mask		255.255.255.0		
IPv4 Default Gateway		172.6.24.1		
IPv6 Address 1		fe80::240:48ff:fe90:cf13/64		
IPv6 Address 2				
IPv6 Default Gateway				
Preferred DNS Server		0.0.0.0		
Alternate DNS Server		0.0.0.0		
Enable DHCP		Disabled		
Enable PPPoE		Disabled		
PPPoE Address				
PPPoE Subnet Mask				
PPPoE Default Gateway				

Figure 12.4 Network Information Interface



### 12.1.5 Viewing HDD Information

**Steps:**

1. Enter the System Information interface.  
Menu > Maintenance > System Info
2. Click the **HDD** tab to enter the HDD Information menu to view the HDD status, free space, property, etc.

Device Info	Camera	Record	Network	HDD		
Label	Status	Capacity	Free Space	Property	Type	Group
5	Normal	931.51GB	927GB	R/W	Local	1
Total Capacity		931.51GB				
Free Space		927GB				

Figure 12.5 HDD Information Interface

## 12.2 Searching & Exporting Log Files

### *Purpose:*

The operation, alarm, exception and information of the device can be stored in log files, which can be viewed and exported at any time.

### *Steps:*

1. Enter the Log Search interface.

Menu > Maintenance > Log Search





Figure 12.6 Log Search Interface

2. Set the log search conditions to refine your search, including the Start Time, End Time, Major Type and Minor Type.
3. Click the **Search** button to start searching log files.
4. The matched log files will be displayed on the list shown below.

**Note:** Up to 2000 log files can be displayed each time.

Log Search		Log Export				
Start Time	05-30-2012		00:00:00			
End Time	05-30-2012		23:59:59			
Major Type	All					
Minor Type	All					
No.	Major Type	Time	Minor Type	Paramet...	Play	Details
1	Operation	05-30-2012 08:43:08	Power On	N/A	—	✓
2	Alarm	05-30-2012 08:43:08	Alarm Input	N/A	—	✓
3	Alarm	05-30-2012 08:43:08	Alarm Input	N/A	—	✓
4	Alarm	05-30-2012 08:43:08	Alarm Input	N/A	—	✓
5	Alarm	05-30-2012 08:43:08	Alarm Input	N/A	—	✓
6	Operation	05-30-2012 08:43:11	Local Operation:...	N/A	—	✓
7	Operation	05-30-2012 08:43:11	Local Operation:...	N/A	—	✓
8	Alarm	05-30-2012 08:43:16	Start Motion Det...	N/A	⏮	✓
9	Alarm	05-30-2012 08:43:55	Stop Motion Det...	N/A	⏮	✓
10	Alarm	05-30-2012 08:43:57	Start Motion Det...	N/A	⏮	✓
11	Alarm	05-30-2012 08:44:11	Stop Motion Det...	N/A	⏮	✓
12	Alarm	05-30-2012 08:44:13	Start Motion Det...	N/A	⏮	✓
13	Alarm	05-30-2012 08:44:32	Stop Motion Det...	N/A	⏮	✓
Total: 352 P: 1/4						

Figure 12.7 Log Search Results

5. You can click the  button of each log or double click it to view its detailed information. And you can also click the  button to view the related video files if available.

Log Information	
Time	05-30-2012 08:52:42
Type	Alarm--Start Motion Detection
Local User	N/A
Host IP Address	N/A
Parameter Type	N/A
Camera No.	A16
Description:	
N/A	
<div>Previous</div> <div>Next</div> <div>OK</div>	

Figure 12.8 Log Details

6. If you want to export the log files, click the **Export** button to enter the Export menu.

You can also export all the log files stored in the HDD.

- (1) Enter the Log Export interface.

Menu > Maintenance > Log Information>Log Export




Figure 12.9 Log Export Interface

- (2) Check ☒ checkbox to select the HDD and click **Export** to enter the export interface.



Figure 12.10 Export Log Files

7. Select the backup device from the dropdown list of **Device Name**.
8. Click the **Export** to export the log files to the selected backup device.

You can click the **New Folder** button to create new folder in the backup device, or click the **Format** button to format the backup device before log export.

**Notes:**

- 1) Please connect the backup device to device before operating log export.
- 2) The log files exported to the backup device are named by exporting time, e.g.,  
20110514124841logBack.txt.

## 12.3 Importing/Exporting Configuration Files

**Purpose:**

The configuration files of the device can be exported to local device for backup; and the configuration files of one device can be imported to multiple device devices if they are to be configured with the same parameters.

**Steps:**

1. Enter the Import/Export Configuration File interface.

Menu > Maintenance > Import/Export




Figure 12.11 Import/Export Config File

2. Click the **Export** button to export configuration files to the selected local backup device.
3. To import a configuration file, select the file from the selected backup device and click the **Import** button.

After the import process is completed, you must reboot the device.

**Note:** After having finished the import of configuration files, the device will reboot automatically.

## 12.4 Upgrading System

### *Purpose:*

The firmware on your device can be upgraded by local backup device or remote FTP server.

### 12.4.1 Upgrading by Local Backup Device

#### *Steps:*

1. Connect your device with a local backup device where the update firmware file is located.
2. Enter the Upgrade interface.  
Menu > Maintenance > Upgrade
3. Click the **Local Upgrade** tab to enter the local upgrade menu.




Figure 12.12 Local Upgrade Interface

4. Select the update file from the backup device.
5. Click the **Upgrade** button to start upgrading.
6. After the upgrading is complete, reboot the device to activate the new firmware.

### 12.4.2 Upgrading by FTP

#### *Before you start:*

Configure PC (running FTP server) and device to the same Local Area Network. Run the 3<sup>rd</sup>-party TFTP software on the PC and copy the firmware into the root directory of TFTP.

#### *Steps:*

1. Enter the Upgrade interface.  
Menu > Maintenance > Upgrade
2. Click the **FTP** tab to enter the local upgrade interface.




Figure 12.13 FTP Upgrade Interface

3. Enter the FTP Server Address in the text field.
4. Click the **Upgrade** button to start upgrading.
5. After the upgrading is complete, reboot the device to activate the new firmware.

## 12.5 Restoring Default Settings

*Steps:*

1. Enter the Default interface.

Menu > Maintenance > Default




Figure 12.14 Restore Factory Default

2. Click the **OK** button to restore the default settings.

**Note:** Except the network parameters (including IP address, subnet mask, gateway, MTU and server port), all other parameters of the device will be restored to factory default settings.



# **C H A P T E R 1 3**

## **Others**

## 13.1 Configuring General Settings

### Purpose:

You can configure the BNC output standard, VGA/HDMI output resolution, mouse pointer speed, etc.

### Steps:

1. Enter the General Settings interface.  
Menu > Configuration > General
2. Select the **General** tab.




Figure 13.1 General Settings Interface

3. Configure the following settings:
  - **Language:** The default language used is *English*.
  - **CVBS Output Standard:** Select the CVBS output standard to NTSC or PAL, which must be the same with the video input standard.
  - **Resolution:** Select the VGA/HDMI output resolution, which must be the same with the resolution of the monitor screen.
  - **Time Zone:** Select the time zone.
  - **Date Format:** Set the date format.
  - **System Date:** Select the system date.
  - **System Time:** Set the system time.
  - **Mouse Pointer Speed:** Set the speed of mouse pointer; 4 levels are configurable.
  - **Enable Wizard:** Enable/disable the Wizard when the device starts up.
  - **Enable ID Authentication:** Enable/disable the use of the login password.
4. Click the **Apply** button to save the settings.

## 13.2 Configuring RS-232 Serial Port

**Note:** The RS-232 serial port is supported by DS-7300HWI/HFI-SH models only.

### Purpose:

The RS-232 port can be used in two ways:

- **Parameters Configuration:** Connect a PC to the device through the PC serial port. Device parameters can be configured by using software such as HyperTerminal. The serial port parameters must be the same as the device's when connecting with the PC serial port.

- Transparent Channel: Connect a serial device directly to the device. The serial device will be controlled remotely by the PC through the network.

**Steps:**

1. Enter the RS-232 Settings interface.

Menu > Configuration > RS-232



The screenshot shows the 'RS-232 Settings' interface with a table of configuration parameters. The title 'RS-232 Settings' is highlighted in yellow. The table has two columns: the parameter name and its current value, with a dropdown arrow on the right of each value.

RS-232 Settings	
Baud Rate	115200
Data Bit	8
Stop Bit	1
Parity	None
Flow Ctrl	None
Usage	Console

Figure 13.2 RS-232 Settings Interface

2. Configure RS-232 parameters, including baud rate, data bit, stop bit, parity, flow control and usage.
3. Click **Apply** to save the settings.


## 13.3 Configuring DST Settings

### Steps:

1. Enter the General Settings interface.

Menu >Configuration>General

2. Choose **DST Settings** tab.



General		<b>DST Settings</b>		More Settings	
<input type="checkbox"/> Auto DST Adjustment					
Enable DST	<input checked="" type="checkbox"/>				
From	Apr	1st	Sun	2	: 00
To	Oct	last	Sun	2	: 00
DST Bias	60 Minutes				

Figure 13.3 DST Settings Interface

You can check the checkbox before the **Auto DST Adjustment** item.

Or you can manually check the Enable DST checkbox, and then set the date of the DST period.

## 13.4 Configuring More Settings

### Steps:

1. Enter the General Settings interface.  
Menu > Configuration > General
2. Click the **More Settings** tab to enter the More Settings interface.




Figure 13.4 More Settings Interface

3. Configure the following settings:
  - **Device Name:** Edit the name of device.
  - **Device No.:** Edit the serial number of device. The Device No. can be set in the range of 1~255, and the default No. is 255.
  - **CVBS Output Brightness:** Adjust the video output brightness.
  - **Operation Timeout:** Set timeout time for menu inactivity. E.g., when the timeout time is set to 5 *Minutes*, the system will exit from the current operation menu to live view screen after 5 minutes of menu inactivity.
  - **Menu Output Mode:** Select the menu output mode to Auto, HDMI/VGA or Main CVBS.

### Notes:

1. When you select **Auto**, the device can automatically detect the HDMI/VGA output as the main output and the CVBS output as the auxiliary output when it starts up.
  2. After you have changed the output mode, you should restart the device to activate the new settings.
4. Click the **Apply** button to save the settings.

## 13.5 Managing User Accounts

### Purpose:

There is a default account in the device: *Administrator*. The *Administrator* user name is *admin* and the password is *12345*. The *Administrator* has the permission to add and delete user and configure user parameters.

### 13.5.1 Adding a User

#### Steps:

1. Enter the User Management interface.

Menu > Configuration > User




Figure 13.5 User Management Interface

2. Click the **Add** button to enter the Add User interface.

The screenshot shows the 'Add User' form. It contains the following fields:

User Name	test02
Password	*****
Confirm	*****
Level	Guest
User's MAC Address	00 :00 :00 :00 :00 :00

At the bottom of the form are two buttons: OK and Cancel.


Figure 13.6 Add User Menu

3. Enter the information for new user, including **User Name**, **Password**, **Level** and **User's MAC Address**.  
**Level:** Set the user level to Operator or Guest. Different user levels have different operating permission.

- **Operator:** The *Operator* user level has permission of Local Log Search in Local Configuration, Remote Log Search and Two-way Audio in Remote Configuration and all operating permission in Camera Configuration.
- **Guest:** The *Guest* user has permission of Local Log Search in Local Configuration, Remote Log Search in Remote Configuration and only has the local/remote playback in the Camera Configuration.

**User's MAC Address:** The MAC address of the remote PC which logs onto the device. If it is configured and enabled, it only allows the remote user with this MAC address to access the device.

- Click the **OK** button to save the settings and go back to the User Management interface. The added new user will be displayed on the list, as shown in Figure 13.6.



No.	User Name	Level	User's MAC Address	Pe...	Edit	Del...
1	admin	Admin	00:00:00:00:00:00	—		—
2	test	Guest	00:00:00:00:00:00			
3	test02	Operator	00:00:00:00:00:00			

Figure 13.7 Added User Listed in User Management Interface

- Select the user from the list and then click the  button to enter the Permission settings interface.



Permission

**Local Configuration**   Remote Configuration   Camera Configuration

- ☒ Local Log Search
- ☒ Local Parameters Settings
- ☒ Local Advanced Operation
- ☒ Local Shutdown / Reboot

Apply   OK   Cancel

Figure 13.8 User Permission Settings Interface

- Set the operating permission of Local Configuration, Remote Configuration and Camera Configuration for the user.

#### Local Configuration

- **Local Log Search:** Searching and viewing logs and system information of device.
- **Local Parameters Settings:** Configuring parameters, restoring factory default parameters and importing/exporting configuration files.
- **Local Advanced Operation:** Operating HDD management (initializing HDD, setting HDD

property), upgrading system firmware, clearing I/O alarm output.

- Local Shutdown /Reboot: Shutting down or rebooting the device.

#### Remote Configuration

- Remote Log Search: Remotely viewing logs that are saved on the device.
- Remote Parameters Settings: Remotely configuring parameters, restoring factory default parameters and importing/exporting configuration files.
- Remote Serial Port Control: Configuring settings for RS-485 ports.
- Remote Video Output Control: Sending remote control panel signal.
- Two-Way Audio: Realizing two-way radio between the remote client and the device.
- Remote Alarm Control: Remotely arming (notify alarm and exception message to the remote client) and controlling the alarm output.
- Remote Advanced Operation: Remotely operating HDD management (initializing HDD, setting HDD property), upgrading system firmware, clearing I/O alarm output.
- Remote Shutdown/Reboot: Remotely shutting down or rebooting the device.

#### Camera Configuration

- Remote Live View: Remotely viewing live video of the selected camera (s).
- Local Manual Operation: Locally starting/stopping manual recording, picture capturing and alarm output of the selected camera (s).
- Remote Manual Operation: Remotely starting/stopping manual recording, picture capturing and alarm output of the selected camera (s).
- Local Playback: Locally playing back recorded files of the selected camera (s).
- Remote Playback: Remotely playing back recorded files of the selected camera (s).
- Local PTZ Control: Locally controlling PTZ movement of the selected camera (s).
- Remote PTZ Control: Remotely controlling PTZ movement of the selected camera (s).
- Local Video Export: Locally exporting recorded files of the selected camera (s).

**Note:** You should select the camera (s) on the Camera Configuration interface for the operation permission configured.

7. Click the **OK** button to save the settings and exit interface.


**Note:** Only the *admin* user account has the permission of restoring factory default parameters.

## 13.5.2 Deleting a User

#### Steps:


1. Enter the User Management interface.  
Menu > Configuration > User
2. Select the user to be deleted from the list.





No.	User Name	Level	User's MAC Address	Pe...	Edit	Del...
1	admin	Admin	00:00:00:00:00:00	—		—
2	test	Guest	00:00:00:00:00:00			
3	test02	Operator	00:00:00:00:00:00			


Figure 13.9 Delete a User

3. Click the  icon to delete the selected user.

### 13.5.3 Editing a User


#### Steps:


1. Enter the User Management interface.  
Menu > Configuration > User
2. Select the user to be edited from the list.



No.	User Name	Level	User's MAC Address	Pe...	Edit	Del...
1	admin	Admin	00:00:00:00:00:00	—		—
2	test	Guest	00:00:00:00:00:00			
3	test02	Operator	00:00:00:00:00:00			

Figure 13.10 Edit a User

3. Click the  icon to enter the Edit User interface.



The 'Edit User' dialog box contains the following fields:

User Name	test
Change Password	<input checked="" type="checkbox"/>
Password	*****
Confirm	*****
Level	Operator
User's MAC Address	00 :00 :00 :00 :00 :00

Buttons at the bottom: Apply, OK, Cancel

Figure 13.11 Edit User Interface

4. Edit the user information, including user name, password, level and MAC address.
5. Click the **OK** button to save the settings and exit the menu.

### 13.5.4 Changing Password of Admin


**Purpose:**

The password of the *admin* user account can be changed in the User Management menu.

**Steps:**

1. Enter the User Management interface.


Menu > Configuration > User




The 'User Management' interface displays a table of users:

No.	User Name	Level	User's MAC Address	Pe...	Edit	Del...
1	admin	Admin	00:00:00:00:00:00	—		—
2	test	Guest	00:00:00:00:00:00			
3	test02	Operator	00:00:00:00:00:00			

Figure 13.12 Change Password

2. Select the *admin* user and click  to change the password.



The screenshot shows a dark-themed 'Edit User' window. It contains a table with the following fields and values:

Edit User	
User Name	admin
Old Password	
Change Password	<input type="checkbox"/>
Password	
Confirm	
User's MAC Address	00 :00 :00 :00 :00 :00

At the bottom of the window are three buttons: 'Apply', 'OK', and 'Cancel'.

Figure 13.13 Change Password

- 
3. Enter the old password, check ☒ checkbox, enter new password and confirm password on the menu.
  4. Click **OK** to save the settings and exit the menu.

## 13.6 Logging out/Shutting down/Rebooting Device

**Steps:**

1. Enter the Shutdown interface.

Menu > Shutdown




Figure 13.14 Shutdown Menu

2. Click the **Logout** button to log out, or  
Click the **Shutdown** button to shut down the device, or  
Click the **Reboot** button to reboot the device.

**Note:** After you have logged out the system, menu operation on the screen is invalid. It is required a user name and password to login the system.

# **C H A P T E R 1 4**

## **Appendix**

## Glossary

- **Dual Stream:** Dual stream is a technology used to record high resolution video locally while transmitting a lower resolution stream over the network. The two streams are generated by the device, with the main stream having a maximum resolution of 4CIF and the sub-stream having a maximum resolution of CIF.
- **DVR:** Acronym for Digital Video Recorder. A DVR is device that is able to accept video signals from analog cameras, compress the signal and store it on its hard drives.
- **HDD:** Acronym for Hard Disk Drive. A storage medium which stores digitally encoded data on platters with magnetic surfaces.
- **DHCP:** Dynamic Host Configuration Protocol (DHCP) is a network application protocol used by devices (DHCP clients) to obtain configuration information for operation in an Internet Protocol network.
- **HTTP:** Acronym for Hypertext Transfer Protocol. A protocol to transfer hypertext request and information between servers and browsers over a network
- **PPPoE:** PPPoE, Point-to-Point Protocol over Ethernet, is a network protocol for encapsulating Point-to-Point Protocol (PPP) frames inside Ethernet frames. It is used mainly with ADSL services where individual users connect to the ADSL transceiver (modem) over Ethernet and in plain Metro Ethernet networks.
- **DDNS:** Dynamic DNS is a method, protocol, or network service that provides the capability for a networked device, such as a router or computer system using the Internet Protocol Suite, to notify a domain name server to change, in real time (ad-hoc) the active DNS configuration of its configured hostnames, addresses or other information stored in DNS.
- **Hybrid DVR:** A hybrid DVR is a combination of a DVR and NVR.
- **NTP:** Acronym for Network Time Protocol. A protocol designed to synchronize the clocks of computers over a network.
- **NTSC:** Acronym for National Television System Committee. NTSC is an analog television standard used in such countries as the United States and Japan. Each frame of an NTSC signal contains 525 scan lines at 60Hz.
- **NVR:** Acronym for Network Video Recorder. An NVR can be a PC-based or embedded system used for centralized management and storage for IP cameras, IP Domes and other DVRs.
- **PAL:** Acronym for Phase Alternating Line. PAL is also another video standard used in broadcast televisions systems in large parts of the world. PAL signal contains 625 scan lines at 50Hz.
- **PTZ:** Acronym for Pan, Tilt, Zoom. PTZ cameras are motor driven systems that allow the camera to pan left and right, tilt up and down and zoom in and out.
- **USB:** Acronym for Universal Serial Bus. USB is a plug-and-play serial bus standard to interface devices to a host computer.

## FAQ

- **Why does my device make a beeping sound after booting?**

The possible reasons for the warning beep on the device are as follows:

- a) There is no HDD installed in the device.
- b) The HDD is not initialized.
- c) HDD error

To cancel the beeping sound and use the device without HDD, enter the Exception Settings interface. For detailed information, see Chapter Handling Exception.

- **Why does the device seem unresponsive when operating with the IR remote control?**

Please read through the section *Using the IR Remote Control*, and check:

- a) The batteries are installed correctly in the remote, making sure that the polarities of the batteries are not reversed.
- b) The batteries are fresh and are not out of power.
- c) The remote has not been tampered with.
- d) There are no fluorescent lamps in use nearby.

- **Why does the PTZ seem unresponsive?**

If the PTZ seem unresponsive, please check:

- a) The RS-485 cable is properly connected.
- b) The dome decoder type is correct.
- c) The dome decoder speed configuration is correct.
- d) The dome decoder address bit configuration is correct.
- e) That the main board RS-485 interface is not broken.

- **Why is there no video recorded after setting the motion detection?**

If there are no recorded video after setting the motion detection, please check:

- a) The recording schedule is setup correctly by following the steps listed in *Configuring Record*.
- b) The motion detection area is configured correctly (See *Configuring Motion Detection*).
- c) The channels are being triggered for motion detection (See *Configuring Motion Detection*).

- **Why doesn't the device detect my USB export device for exporting recorded files?**

There's a chance that the device and your USB device is not compatible. Please refer to our company's website to view a list of compatible devices.

- **My device is in Live View mode and the menu does not show up. It does not respond to the mouse or the IR remote control.**

Your device may be in auxiliary mode. This occurs when the **Main/Spot** on front panel or **VOIP** button on IR remote control is pressed. To return to the previous mode of operation, press the **Main/Spot** or **VOIP** button again and then press **Enter** button on the IR remote control.